

PROIECT NR. :TE-119/2015

**INVESTITIA : "INLOCUIRE CONDUCTA TITEI $\varnothing 4^{1/2}$ " + $\varnothing 8^{5/8}$ " COMANESTI-VERMESTI
IN ZONELE SUBTRAVERSARE LINIE CF SI DN PE O LUNGIME DE CIRCA 238m SI IN
ZONA PARAU URMENIS – SPATE TERMOCENTRALA PE O LUNGIME DE CIRCA
450m" **ZONA II – PARAU URMENIS – SPATE TERMOCENTRALA****

**ANTEMASURATOARE : 253904 - AMENAJARE TEREN TRASEU CONDUCTA
EXISTENTA $\varnothing 4^{1/2}$ " CARE SE VA DEMONTA, IN ZONA IN CARE CELE DOUA
CONDUCTE NU AU CULOAR COMUN**

NR CRT	SIMBOL ARTICOL	DENUMIRE, SPORURI	U.M.	CANT.	CALCUL CANTITATI
1	TSH01A1	Curatare teren de craci, gunoi, pietre	100 m ²	7.44	186m x 4m = 744m ² (pentru restul traseului, conductele au culoar comun)
2	NMB319721	Montaj folie geotextila	ore	4	
3	7461776	Folie geotextila	m ²	372	186m x 2m
4	TSA01B1	Decopertare manula strat vegetal	m ³	112	186m x 2m = 372m ² x 0.30m = 112m ³
5	TRB04B2	Aducere manuala strat vegetal	to	191	112m ³ x 1.7
6	TSE01B1	Nivelare manuala strat vegetal	100 m ²	3.72	186m x 2m = 372m ²
7	TSH13B1	ingrasaminte	to	0.008	186m x 2m = 372m ² = 0.037Ha x 0.2to/Ha
8	TSH09A1	Semanare sup. decopertata	100 m ²	3.72	186m x 2m = 372m ²
9	TSD14A1	Udare semanaturi	m ³	1.9	0.5m ³ /100m ²
10	TRA05A10	Transport apa pentru insamantari teren	to	1.9	