

PROIECT NR. :TE-119/2015

**INVESTITIA : “INLOCUIRE CONDUCTA TITEI Ø4^{1/2}” + Ø8^{5/8}” COMANESTI-VERMESTI
IN ZONELE SUBTRAVERSARE LINIE CF SI DN PE O LUNGIME DE CIRCA 238m SI IN
ZONA PARAU URMENIS – SPATE TERMOCENTRALA PE O LUNGIME DE CIRCA
450m” ZONA I – SUBTRAVERSARE LINIE CF SI DN**

**ANTEMASURATOARE : 253805 - SUBTRAVERSARE CF SI DN CU CONDUCTA Ø4^{1/2}”
(TUB PROTECTIE, INSTALATIE DE SCURGERE SI AERISIRE)**

NR CRT	SIMBOL ARTICOL	DENUMIRE, SPORURI	U.M.	CANT.	CALCUL CANTITATI
1	GA09A1	Saparea tunelului, imbinarea si introducerea tevii de protectie	m	83	
2	2600294	Scad bitum	kg	-13.28	
3	2600282	Scad bitum	kg	-926.28	
4	AUT4030	Scad topitor de bitum	ore	-4.98	
5	3278517	teava 273.0x8mm L245 PSL1	m	84.7	83m x 1.02(pierdere)
6	IZL04B1	Montaj inele distantiere <u>Spor: -100% mat.</u>	m	83	
7	7454771	Inele distantiere 4”-10”	buc	85	
8	M1G12A1	Montaj presetupe (2 buc)	to	0.020	
9	3278518	Presetupa 4inch – 10inch	buc	2	
10	GA11A1	Instalatie scurgere si aerisire (inclusiv sapare sant, gropi pentru recipient, preparare si turnare beton pentru soclu)	buc	1	
11	2600282	Scad bitum	kg	-75	
12	6718518	Scad banda protectie	m ²	-16	
13	3117177	Scad teava scurgere	m	-41.2	
14	2600294	Scad bitum	kg	-2.2	
15	3278519	Teava 60.3 x 3.5mm L210	m	17	
16	6310172	Instalatie de aerisire (confectionie metalica)	kg	150	
17	3278520	Camin colectare scurgeri 521 x 7.14mm , h = 3.5m	buc	1	
18	M1J04B1	Confectionare instalatie de aerisire	to	0.150	
19	M1J04D1	Confectionare camin scurgeri	to	0.548	
20	IZA01B1	Sablare instalatie de aerisire (1mp) si camin(0.4mp), in vederea vopsirii	m ²	1.4	
21	IZD08B1	Vopsire inst. de aerisire si camin <u>Spor: -100% mat.</u>	m ²	2.8	2.8 m ² x 2 straturi
22	6100091	Grund (2 straturi)	kg	0.4	
23	6100092	Email (2 straturi)	kg	0.3	

24	NMB222791	Control vizual	ore	2	
25	TSA07C1	Gropi pentru foreza h<2m	m ³	123	10m x 6m x 1.7m(2m-0.30m) + 3m x 4m x 1.7m(2m-0.30m)
26	TSA07F1	Gropi pentru foreza h>2m	m ³	36	10m x 6m x 0.5m + 3m x 4m x 0.5m
27	TSF03B1	Sprijinire maluri	m ²	58	10m x 2.2m(2.5m-0.30m) x 2buc + 3m x 2.2m(2.5m-0.30m) x 2buc
28	DA05A1	Pamant cernut	m ³	16	159 m ³ x 10%
29	TSD01C1	Astupare gropi foreza	m ³	159	
30	TSD04D1	Compactare gropi foreza	m ³	159	
31	AUT6751	Macara 5tf	ore	4	
32	TRA05A10	Transport apa ptr. compactare	to	15.9	0.1 m ³ apa / m ³ pamant
33	TRI1AC07E1	Incarcare materiale	to	5.5	
34	TRA04A10	Transport materiale la santier	to	5.5	
35	TRI1AC15E1	Descarcare materiale	to	5.5	
36	MDTC4622050	Transport macara la si de la santier	buc	1	