

**PROIECT NR. :TE-119/2015**

**INVESTITIA : “INLOCUIRE CONDUCTA TITEI Ø4<sup>1/2</sup>” + Ø8<sup>5/8</sup>” COMANESTI-VERMESTI  
IN ZONELE SUBTRAVERSARE LINIE CF SI DN PE O LUNGIME DE CIRCA 238m SI IN  
ZONA PARAU URMENIS – SPATE TERMOCENTRALA PE O LUNGIME DE CIRCA  
450m” ZONA II – PARAU URMENIS – SPATE TERMOCENTRALA**

**ANTEMASURATOARE : 253904 - AMENAJARE TEREN TRASEU CONDUCTA  
EXISTENTA Ø4<sup>1/2</sup>” CARE SE VA DEMONTA, IN ZONA IN CARE CELE DOUA  
CONDUCTE NU AU CULOAR COMUN**

NR CRT	SIMBOL ARTICOL	DENUMIRE, SPORURI	U.M.	CANT.	CALCUL CANTITATI
1	TSH01A1	Curatare teren de craci, gunoi, pietre	100 m <sup>2</sup>	7.44	186m x 4m = 744m <sup>2</sup> ( pentru restul traseului, conductele au culoar comun )
2	NMB319721	Montaj folie geotextila	ore	4	
3	7461776	Folie geotextila	m <sup>2</sup>	372	186m x 2m
4	TSA01B1	Decopertare manula strat vegetal	m <sup>3</sup>	112	186m x 2m = 372m <sup>2</sup> x 0.30m = 112m <sup>3</sup>
5	TRB04B2	Aducere manuala strat vegetal	to	191	112m <sup>3</sup> x 1.7
6	TSE01B1	Nivelare manuala strat vegetal	100 m <sup>2</sup>	3.72	186m x 2m = 372m <sup>2</sup>
7	TSH13B1	ingrasaminte	to	0.008	186m x 2m = 372m <sup>2</sup> = 0.037Ha x 0.2to/Ha
8	TSH09A1	Semanare sup. decopertata	100 m <sup>2</sup>	3.72	186m x 2m = 372m <sup>2</sup>
9	TSD14A1	Udare semanaturi	m <sup>3</sup>	1.9	0.5m <sup>3</sup> /100m <sup>2</sup>
10	TRA05A10	Transport apa pentru insamantari teren	to	1.9	