

PROIECT NR. :TE-119/2015

**INVESTITIA : "INLOCUIRE CONDUCTA TITEI $\varnothing 4^{1/2}$ " + $\varnothing 8^{5/8}$ " COMANESTI-VERMESTI
IN ZONELE SUBTRAVERSARE LINIE CF SI DN PE O LUNGIME DE CIRCA 238m SI IN
ZONA PARAU URMENIS – SPATE TERMOCENTRALA PE O LUNGIME DE CIRCA
450m" ZONA II – PARAU URMENIS – SPATE TERMOCENTRALA**

**ANTEMASURATOARE : 253902 - DESFACEREA SI REFACEREA DRUMULUI
PIETRUIT LA SUBTRAVERSAREA CU CONDUCTA $\varnothing 4^{1/2}$ "**

NR CRT	SIMBOL ARTICOL	DENUMIRE, SPORURI	U.M.	CANT.	CALCUL CANTITATI
1	DG01A1	Desfacere drum (cu pastrarea pietrei existente)	m ²	8	4m x 2m
2	TSE06B1	Nivelare si compactare drum	100 m ²	0.08	
3	DA06A1	Refacere drum cu piatra existenta	m ³	1.6	4m x 2m x 0.20m
4	2200379	Scad balast	m ³	-2.097	
5	3278342	Completare piatra existenta	m ³	0.5	
6	TSA19B1	Refacere rigole	m ³	0.4	
7	ACE16A1	Podet peste sant	m	4	
8	DF24A1	Semnalizare rutiera	pct	1	
9	TRA05A10	Transport apa ptr. compactare	to	0.47	
10	TRA01A30	Transport 0.5m ³ piatra	to	0.750	