

PROIECT NR. :TE-119/2015

**INVESTITIA : “INLOCUIRE CONDUCTA TITEI Ø4^{1/2}” + Ø8^{5/8}” COMANESTI-VERMESTI
IN ZONELE SUBTRAVERSARE LINIE CF SI DN PE O LUNGIME DE CIRCA 238m SI IN
ZONA PARAU URMENIS – SPATE TERMOCENTRALA PE O LUNGIME DE CIRCA
450m” ZONA II – PARAU URMENIS – SPATE TERMOCENTRALA**

**ANTEMASURATOARE : 253907 - SUBTRAVERSARE DRUM PIETRUIT CU
CONDUCTA Ø4^{1/2}” (TUB PROTECTIE)**

NR CRT	SIMBOL ARTICOL	DENUMIRE, SPORURI	U.M.	CANT.	CALCUL CANTITATI
1	GA08B1	Imbinarea si montarea tevii de protectie	m	6	
2	2600294	Scad bitum	kg	-0.9	
3	2600282	Scad bitum	kg	-34.8	
4	6718518	Scad banda PVC	m ²	-6	
5	AUT7002	Scad macara lansator de cond.	ore	-2.04	
6	AUT4030	Scad topitor de bitum	ore	-0.36	
7	3278517	teava 273.0x8mm L245 PSL1	m	6.2	6m x 1.02(pierdere)
8	IZL04B1	Montaj inele distantiere <i>Spor: -100% mat.</i>	m	6	
9	7454771	Inele distantiere 4"-10"	buc	5	
10	M1G12A1	Montaj presetupe (2 buc)	to	0.020	
11	3278518	Presetupa 4inch – 10inch	buc	2	
12	NMB222791	Control vizual	ore	1	
13	TSC04B1	Sapatura pentru tub protectie	100 m ³	0.08	6m x 1m x 1.33m
14	DA05A1	Pamant cernut	m ³	1	8 m ³ x 10%
15	TSD03C1	Astupare sant	100 m ³	0.08	
16	TSD05B1	Compactare sant	100 m ³	0.08	
17	AUT6751	Macara 5tf	ore	4	
18	TRA05A10	Transport apa ptr. compactare	to	0.8	0.1 m ³ apa / m ³ pamant
19	TRI1AC07E1	Incarcare materiale	to	0.370	
20	TRA02A10	Transport materiale la santier	to	0.370	
21	TRI1AC15E1	Descarcare materiale	to	0.370	