

PROIECT NR. :TE-119/2015

**INVESTITIA : “INLOCUIRE CONDUCTA TITEI $\varnothing 4^{1/2}$ ” + $\varnothing 8^{5/8}$ ” COMANESTI-VERMESTI
IN ZONELE SUBTRAVERSARE LINIE CF SI DN PE O LUNGIME DE CIRCA 238m SI IN
ZONA PARAU URMENIS – SPATE TERMOCENTRALA PE O LUNGIME DE CIRCA
450m” ZONA I – SUBTRAVERSARE LINIE CF SI DN**

**ANTEMASURATOARE : 253802 - AMENAJARE TEREN TRASEU CONDUCTA
PROIECTATA $\varnothing 4^{1/2}$ ”**

NR CRT	SIMBOL ARTICOL	DENUMIRE, SPORURI	U.M.	CANT.	CALCUL CANTITATI
1	TSH01A1	Curatare teren de craci, gunoi, pietre	100 m ²	3.68	129m – 83m(traversare) = 46m x 8m = 368m ²
2	NMB319721	Montaj folie geotextila	ore	1	
3	7461776	Folie geotextila	m ²	92	46m x 2m
4	TSA01B1	Decopertare manuala strat vegetal	m ³	83	129m – 83m(traversare) = 46m x 6m = 276m ² x 0.30m = 83m ³
5	TRB04B2	Aducere manuala strat vegetal	to	141	83m ³ x 1.7
6	TSE01B1	Nivelare manuala strat vegetal	100 m ²	2.76	129m – 83m(traversare) = 46m x 6m = 276m ²
7	TSH13B1	ingrasaminte	to	0.006	46m x 6m = 276m ² = 0.027Ha x 0.2to/Ha
8	TSH09A1	Semanare sup. decopertata	100 m ²	2.76	46m x 6m = 276m ²
9	TSD14A1	Udare semanaturi	m ³	1.4	0.5m ³ /100m ²
10	M2I15A	Panou protectia muncii	m ²	1	
11	TRA05A10	Transport apa pentru insamantari teren	to	1.4	