

**PROIECT NR. :TE-119/2015**

**INVESTITIA : "INLOCUIRE CONDUCTA TITEI Ø4<sup>1/2"</sup> + Ø8<sup>5/8"</sup> COMANESTI-VERMESTI  
IN ZONELE SUBTRAVERSARE LINIE CF SI DN PE O LUNGIME DE CIRCA 238m SI IN  
ZONA PARAU URMENIS – SPATE TERMOCENTRALA PE O LUNGIME DE CIRCA  
450m" ZONA II – PARAU URMENIS – SPATE TERMOCENTRALA**

**ANTEMASURATOARE : 253907 - SUBTRAVERSARE DRUM PIETRUIT CU  
CONDUCTA Ø4<sup>1/2"</sup> ( TUB PROTECTIE )**

| NR CRT | SIMBOL ARTICOL | DENUMIRE, SPORURI                                          | U.M.               | CANT. | CALCUL CANTITATI                               |
|--------|----------------|------------------------------------------------------------|--------------------|-------|------------------------------------------------|
| 1      | GA08B1         | Imbinarea si montarea tevii de protectie                   | m                  | 6     |                                                |
| 2      | 2600294        | Scad bitum                                                 | kg                 | -0.9  |                                                |
| 3      | 2600282        | Scad bitum                                                 | kg                 | -34.8 |                                                |
| 4      | 6718518        | Scad banda PVC                                             | m <sup>2</sup>     | -6    |                                                |
| 5      | AUT7002        | Scad macara lansator de cond.                              | ore                | -2.04 |                                                |
| 6      | AUT4030        | Scad topitor de bitum                                      | ore                | -0.36 |                                                |
| 7      | 3278517        | teava 273.0x8mm L245 PSL1                                  | m                  | 6.2   | 6m x 1.02(pierdere)                            |
| 8      | IZL04B1        | Montaj inele distantiere<br><b><u>Spor: -100% mat.</u></b> | m                  | 6     |                                                |
| 9      | 7454771        | Inele distantiere 4"-10"                                   | buc                | 5     |                                                |
| 10     | M1G12A1        | Montaj presetupe ( 2 buc )                                 | to                 | 0.020 |                                                |
| 11     | 3278518        | Presetupa 4inch – 10inch                                   | buc                | 2     |                                                |
| 12     | NMB222791      | Control vizual                                             | ore                | 1     |                                                |
| 13     | TSC04B1        | Sapatura pentru tub protectie                              | 100 m <sup>3</sup> | 0.08  | 6m x 1m x 1.33m                                |
| 14     | DA05A1         | Pamant cernut                                              | m <sup>3</sup>     | 1     | 8 m <sup>3</sup> x 10%                         |
| 15     | TSD03C1        | Astupare sant                                              | 100 m <sup>3</sup> | 0.08  |                                                |
| 16     | TSD05B1        | Compactare sant                                            | 100 m <sup>3</sup> | 0.08  |                                                |
| 17     | AUT6751        | Macara 5tf                                                 | ore                | 4     |                                                |
| 18     | TRA05A10       | Transport apa ptr. compactare                              | to                 | 0.8   | 0.1 m <sup>3</sup> apa / m <sup>3</sup> pamant |
| 19     | TRI1AC07E1     | Incarcare materiale                                        | to                 | 0.370 |                                                |
| 20     | TRA02A10       | Transport materiale la santier                             | to                 | 0.370 |                                                |
| 21     | TRI1AC15E1     | Descarcare materiale                                       | to                 | 0.370 |                                                |