

PROIECT NR. :TE-121/2015

INVESTITIA : "CONDUCTA TRANSPORT TITEI Ø10^{3/4"} GHERCESTI – ICOANA, IN 3 TRONSOANE" TRONSON I – IESIRE STATIE, SUBTRAVERSARE DC CRAIOVA - GHERCESTI

ANTEMASURATOARE : 255711 - AMENAJARE TEREN TRASEU CONDUCTA EXISTENTA Ø10^{3/4"}, CARE SE VA DEMONTA

NR CRT	SIMBOL ARTICOL	DENUMIRE, SPORURI	U.M.	CANT.	CALCUL CANTITATI
1	TSH01A1	Curatare teren de craci, gunoi, pietre	100 m ²	46.56	426m – 30m(incinta) – 8m(drum) = 388m x 12m = 4656m ²
2	NMB319721	Montaj folie geotextila	ore	8	
3	7461776	Folie geotextila	m ²	752	426m – 30m(incinta) – 20m(foraj) = 376m x 2m
4	TSA01D1	Decopertare manula strat vegetal	m ³	30	10m(zona DC) x 10m = 100m ² x 0.30m = 30m ³
5	TSC19B1	Decopertare mecanizata strat vegetal 426m – 30m(incinta) – 20m(foraj) – 10m(dec. man.) = 366m	100 m ³	10.98	366m x 10m = 3660m ² x 0.30m = 1098m ³
6	TRB04B2	Aducere manuala strat vegetal	to	51	30m ³ x 1.7
7	TSE01D1	Nivelare manuala strat vegetal	100 m ²	1.00	10m x 10m = 100m ²
8	TSC26B1	Aducere mecanizata strat vegetal (5m)	100 m ³	10.98	366m x 10m = 3660m ² x 0.30m = 1098m ³
9	TSC27B1	Spor ptr. aducere mecanizata strat vegetal inca 5m	100 m ³	5.49	1098m ³ : 2
10	TSE04B1	Nivelare mecanizata strat vegetal	100 m ²	36.60	366m x 10m = 3660m ²
11	M2I15A	Panou protectia muncii	m ²	1	
12	TRA04B50	Asimilat cu transport buldozer	to	20	