

**PROIECT NR. :TE-121/2015**

**INVESTITIA : "CONDUCTA TRANSPORT TITEI Ø10<sup>3/4"</sup> GHERCESTI – ICOANA, IN 3 TRONSOANE" TRONSON I – IESIRE STATIE, SUBTRAVERSARE DC CRAIOVA - GHERCESTI**

**ANTEMASURATOARE : 255702 - AMENAJARE TEREN TRASEU CONDUCTA PROIECTATA Ø10<sup>3/4"</sup>**

| NR CRT | SIMBOL ARTICOL | DENUMIRE, SPORURI  | U.M.               | CANT. | CALCUL CANTITATI  |
|--------|----------------|--|--------------------|-------|---|
| 1      | TSH01A1        | Curatare teren de craci, gunoi, pietre   | 100 m <sup>2</sup> | 46.56 | 426m – 30m(incinta) – 8m(drum) = 388m x 12m = 4656m <sup>2</sup>                    |
| 2      | NMB319721      | Montaj folie geotextila  | ore                | 8     |   |
| 3      | 7461776        | Folie geotextila   | m <sup>2</sup>     | 752   | 426m – 30m(incinta) – 20m(foraj) = 376m x 2m  |
| 4      | TSA01D1        | Decopertare manula strat vegetal   | m <sup>3</sup>     | 30    | 10m(zona gropii pentru foreza) x 10m = 100m <sup>2</sup> x 0.30m = 30m <sup>3</sup> |
| 5      | TSC19B1        | Decopertare mecanizata strat vegetal<br>426m – 30m(incinta) – 20m(foraj) – 10m(dec. man.) = 366m | 100 m <sup>3</sup> | 10.98 | 366m x 10m = 3660m <sup>2</sup><br>x 0.30m = 1098m <sup>3</sup>                     |
| 6      | TRB04B2        | Aducere manuala strat vegetal  | to                 | 51    | 30m <sup>3</sup> x 1.7  |
| 7      | TSE01D1        | Nivelare manuala strat vegetal   | 100 m <sup>2</sup> | 1.00  | 10m x 10m = 100m <sup>2</sup>   |
| 8      | TSC26B1        | Aducere mecanizata strat vegetal ( 5m )  | 100 m <sup>3</sup> | 10.98 | 366m x 10m = 3660m <sup>2</sup><br>x 0.30m = 1098m <sup>3</sup>                     |
| 9      | TSC27B1        | Spor ptr. aducere mecanizata strat vegetal inca 5m   | 100 m <sup>3</sup> | 5.49  | 1098m <sup>3</sup> : 2  |
| 10     | TSE04B1        | Nivelare mecanizata strat vegetal  | 100 m <sup>2</sup> | 36.60 | 366m x 10m = 3660m <sup>2</sup>   |
| 11     | M2I15A         | Panou protectia muncii   | m <sup>2</sup>     | 1     |   |
| 12     | TRA04B50       | Asimilat cu transport buldozer   | to                 | 20    |   |