

PROIECT NR. :TE-121/2015

INVESTITIA : "CONDUCTA TRANSPORT TITEI Ø10^{3/4"} GHERCESTI – ICOANA, IN 3 TRONSOANE" TRONSON II – MAL DREPT PARAU TESLUI – FOSTA ALBIE A PARAULUI

ANTEMASURATOARE : 255804 - SUBTRAVERSAREA PRIN FORAJ ORIZONTAL A PARAULUI TESLUI, CU CONDUCTA Ø10^{3/4"} x 120m

NR CRT	SIMBOL ARTICOL	DENUMIRE, SPORURI	U.M.	CANT.	CALCUL CANTITATI
1	GA09A1	Asimilat cu saparea tunelului si introducerea conductei <u>Spor: -100% mat. ; +100%man.; +100%util.</u>	m	120	
2	AUT4030	Scad topitor de bitum	ore	-7.2	
3	AUT3006	Scad grup termic de sudura	ore	-25.2	
4	M1J04C1	Asamblarea tevii care se va monta prin F.O. (120m)	to	5.7	
5	6202818	Scad apa industriala	m ³	-3.42	
6	AUT2505	Scad compresor	ore	-0.171	
7	AUT3304	Scad electropompa	ore	-2.565	
8	3278576	Teava preizolata 273.0x7.1mm L360N PSL2	m	121	120m x 1.003
9	GB03G1	Montaj robinet	buc	2	
10	3278544	Robinet cu sertar Dn250 Pn63	buc	2	
11	GB05G1	Montaj flanse	buc	4	
12	3278545	Flansa cu gat Dn250 Pn63 P285NH	buc	4	
13	GB06G1	Asamblare flanse <u>Spor : - 100% mat.</u>	per	4	
14	3278546	Garnitura spirometalica Dn250 Pn63	buc	4	
15	3278547	Prezon M33x 200 42CrMo4QT	buc	48	
16	3278548	Piulita M33 42CrMo4QT	buc	96	
17	M1J04D1	Confectionare protector robinet	to	0.260	
18	3277477	Protector robinet (materiale)	buc	2	
19	GB08B1	Montaj protector robinet <u>Spor : - 100% mat.</u>	buc	2	
20	AUT4030	Scad topitor bitum	ore	-0.22	
21	IZA01B1	Sablare protector robinet (2.5mp/buc), in vederea vopsirii	m ²	5	
22	IZD08B1	Vopsire protector robinet <u>Spor: -100% mat.</u>	m ²	10	5m ² x 2 straturi
23	6100091	Grund (2 straturi)	kg	1.3	
24	6100092	Email (2 straturi)	kg	1.15	

25	M1L24A1	Polizare suduri	m	13	
26	M1L05C1	Gamagrafiere suduri 10" 20% in fir curent si 100% la traversari si cuplari	buc	15	Suduri 10" = 120m : 12m + 4 flanse
27	NMB222791	Control vizual suduri	ore	1	
28	M1J38A1	Poansonare suduri	buc	15	
29	TSA07D1	Gropi pentru foreza h<2m	m ³	133	10m x 6m x 1.7m(2m- 0.30m) + 3m x 6m x 1.7m(2m – 0.30m)
30	TSA07G1	Gropi pentru foreza h>2m	m ³	39	10m x 6m x 0.5m + 3m x 6m x 0.5m
31	TSF03B1	Sprijinire maluri	m ²	58	10m x 2.2m(2.5m- 0.30m) x 2buc + 3m x 2.2(2.5m – 0.30m) x 2buc
32	DA05A1	Pamant cernut	m ³	18	172 m ³ x 10%
33	TSD01D1	Astupare gropi foreza	m ³	172	
34	TSD04D1	Compactare gropi foreza	m ³	172	
35	TSA23A1	Epuizarea apelor din sapaturi	m ³	18	172 m ³ x 10%
36	AUT6751	Macara 5tf	ore	8	
37	TRA05A10	Transport apa ptr. compactare	to	17.2	0.1 m ³ apa / m ³ pamant
38	TRI1AC07E1	Incarcare materiale	to	7	
39	TRA04A25	Transport materiale la santier	to	7	
40	TRI1AC15E1	Descarcare materiale	to	7	
41	MDTC4622050	Transport macara la si de la santier	buc	1	