

PROIECT NR. :TE-121/2015

INVESTITIA : "CONDUCTA TRANSPORT TITEI Ø10^{3/4"} GHERCESTI – ICOANA, IN 3 TRONSOANE" TRONSON II – MAL DREPT PARAU TESLUI – FOSTA ALBIE A PARAULUI

ANTEMASURATOARE : 255811 - AMENAJARE TEREN TRASEU CONDUCTA EXISTENTA Ø10^{3/4"}, CARE SE VA DEMONTA

NR CRT	SIMBOL ARTICOL	DENUMIRE, SPORURI	U.M.	CANT.	CALCUL CANTITATI
1	TSH01A1	Curatare teren de craci, gunoi, pietre	100 m ²	27.60	250m – 20m(parau) = 230m x 12m = 2760m ²
2	NMB319721	Montaj folie geotextila	ore	4	
3	7461776	Folie geotextila	m ²	260	250m – 120m(foraj) = 130m x 2m
4	TSA01D1	Decopertare manula strat vegetal	m ³	39	13m(zona parau) x 10m = 130m ² x 0.30m = 39m ³
5	TSC19B1	Decopertare mecanizata strat vegetal	100 m ³	3.51	250m – 13m(dec.man) – 120m(foraj) = 117m x 10m = 1170m ² x 0.30m = 351m ³
6	TRB04B2	Aducere manuala strat vegetal	to	66.3	39m ³ x 1.7
7	TSE01D1	Nivelare manuala strat vegetal	100 m ²	1.30	13m x 10m = 130m ²
8	TSC26B1	Aducere mecanizata strat vegetal (5m)	100 m ³	3.51	250m – 13m(dec.man) – 120m(foraj) = 117m x 10m = 1170m ² x 0.30m = 351m ³
9	TSC27B1	Spor ptr. aducere mecanizata strat vegetal inca 5m	100 m ³	1.75	351m ³ : 2
10	TSE04B1	Nivelare mecanizata strat vegetal	100 m ²	11.70	250m – 13m(dec.man) – 120m(foraj) = 117m x 10m = 1170m ²
11	M2I15A	Panou protectia muncii	m ²	1	
12	TRA04B50	Asimilat cu transport buldozer	to	20	