

PROIECT NR. :TE-121/2015

INVESTITIA : "CONDUCTA TRANSPORT TITEI Ø10^{3/4"} GHERCESTI – ICOANA, IN 3 TRONSOANE" TRONSON III – VALEA DRAGHIEI

ANTEMASURATOARE : 255903 - AMENAJARE TEREN TRASEU CONDUCTA PROIECTATA Ø10^{3/4"}

NR CRT	SIMBOL ARTICOL	DENUMIRE, SPORURI	U.M.	CANT.	CALCUL CANTITATI
1	TSH01A1	Curatare teren de craci, gunoi, pietre	100 m ²	30.60	258m – 3m(drum) = 255m x 12m = 3060m ²
2	NMB319721	Montaj folie geotextila	ore	6	
3	7461776	Folie geotextila	m ²	510	258m – 3m(drum) = 255m x 2m
4	TSC19B1	Decopertare mecanizata strat vegetal	100 m ³	7.65	258m – 3m(drum) = 255m x 10m = 2550m ² x 0.30m = 765m ³
5	TSC26B1	Aducere mecanizata strat vegetal (5m)	100 m ³	7.65	258m – 3m(drum) = 255m x 10m = 2550m ² x 0.30m = 765m ³
6	TSC27B1	Spor ptr. aducere mecanizata strat vegetal inca 5m	100 m ³	3.83	765m ³ : 2
7	TSE04B1	Nivelare mecanizata strat vegetal	100 m ²	25.50	258m – 3m(drum) = 255m x 10m = 2550m ²
8	M2I15A	Panou protectia muncii	m ²	1	
9	TRA04B50	Asimilat cu transport buldozer	to	20	