

PROIECT NR. : TE-121/2015

INVESTITIA : "CONDUCTA TRANSPORT TITEI Ø10^{3/4}" GHERCESTI – ICOANA, IN 3 TRONSOANE" TRONSON III – VALEA DRAGHIEI

ANTEMASURATOARE : 255904 - MONTAJ CONDUCTA Ø10^{3/4}" x 256m

NR CRT	SIMBOL ARTICOL	DENUMIRE, SPORURI	U.M.	CANT.	CALCUL CANTITATI
1	TSA14D1	Gropi prizare la capetele cond.	m ³	34	5m x 2m x 1.7m x 2buc
2	TSF02B1	Sprijinire maluri	m ²	34	5m x 1.7m x 4maluri
3	TSC04B1	Sapatura mecanizata cond.	100 m ³	2.84	251m x (1.2m+0.6m)/2 x 1.2m(1.5m – 0.30m) + 5m(drum) x 1.4m x 1.8m
4	TSF03B1	Sprijinire maluri	m ²	18	5m x 1.8m x 2maluri
5	TSE01D1	Nivelare manuala fund sant la sapatura mecanizata	100 m ²	1.57	251m x 0.6m + 5m x 1.4m
6	GD09B1%	Nisip 10cm sub si peste conducta	m ³	67	251m x 0.6m x 0.5m + 5m x 1.4m x 0.5m – vol.cd.proiectata
7	DA05A1	Pamant cernut 10%	m ³	32	
8	TSD01D1	Astupare sant manual	m ³	34	
9	TSD03C1	Astupare sant mecanizat	100 m ³	2.84	
10	TSD04D1	Compactare manuala	m ³	34	
11	TSD05B1	Compactare mecanizata	100 m ³	2.84	
12	GA04D1	Montaj conducta	hm	2.56	
13	2600294	Scad bitum	kg	-1.024	
14	2600282	Scad bitum	kg	-22.528	
15	2601913	Scad impaslitura	m ²	-10.24	
16	2601664	Scad carton bitumat	m ²	-5.12	
17	AUT4030	Scad topitor bitum	ore	-0.514	
18	3278607	Teava preizolata 273.0x6.3mm L360N PSL2	m	257	256m x 1.003
19	GD04F1	Cuplare la cond. existenta	buc	2	
20	NMB019621	Man. montaj banda avertizoare	ore	4	
21	7106636	Banda avertizoare	m	277	256m x 1.08
22	GD05E1	Montaj curbe 10"	buc	4	
23	3278577	Curba 30gr 5Dn 273.0x8mm L360N	buc	4	
24	M1L82A1	Probe martor suduri	m	1	1% din nr. suduri
25	M1L24A1	Polizare suduri	m	26	30 sud. x 0.86m/sud.

26	M1L05C1	Gamagrafiere suduri 10" 20% in fir curent si 100% la traversari si cuplari	buc	13	Suduri 10" = 256m : 12m + 4curbe x 1.5 + 2cuplari
27	NMB222791	Control vizual suduri	ore	2	
28	M1J38A1	Poansonare suduri	buc	30	
29	GC05G1	Probele hidraulice pentru conducta proiectata	hm	2.56	
30	GC06G1	Proba tronson la traversari	buc	1	
31	AUT2920	cimentruc	ore	8	
32	TFC02F1	Curatarea conductei	m	256	
33	GC04G1	Montare si demontare echipament pentru curatare	buc	1	
34	3278536	Piston cu perii 10"	buc	1	
35	2222240	Dispozitiv spalare conducta	buc	2	
36	DF18B1	Montaj indicatori directie	buc	4	
37	3270001	Indicator directie traseu conducta	buc	4	
38	DH18B1	Scriere indicatori directie	buc	4	
39	AUT6751	Macara 5Tf	ore	4	
40	TRA04B50	Asimilat cu transport utilaje (cimentruc, excavator, macara lansator de conducte)	to	72	
41	TRA01A30	Transport nisip	to	104	
42	TRA05A10	Transport apa ptr. compactare (31.8mc), spalare cond (26.624mc) si probe cond. (21.822mc)	to	81	Calcul conform consumurilor prevazute in normele de deviz
43	TRI1AC07E1	Incarcare materiale	to	11.5	
44	TRI1AC15E1	Descarcare materiale	to	11.5	
45	TRA04A25	Transport materiale	to	11.5	
46	MDTC4622050	Transport macara la si de la santier	buc	1	