

Proiectant: SC PETROSTAR SA PLOIESTI
 OBIECTIV: 48M.2 - 160/4921 ET. 2+4 REV. 1 INLOCUIRE CONDUCTA TITEI Ø 10 3/4 INCH SILISTE - PLOIESTI, IN ZONA STADION BRAZI - INTERIOR RAFINARIE PETROBRAZI, PE O LUNGIME DE CCA 1170 M SI INLOCUIRE INSTALATIE CURATITOARE

FORMULARUL F4cp - LISTA cu cantitatile de utilaje si echipamente tehnologice, inclusiv dotari si active necorporale

						- lei -
Nr. crt.	Denumirea	U.M.	Cantitatea	Pret unitar - lei/um -	Valoarea (exclusiv TVA) - lei -	Fisa tehnica atasata
0	1	2	3	4	5 = 3 x 4	6

7 - INSTALATIE DE PRIMIRE CURATITOARE Ø 10 INCH, 300# - Lista echipamente

1	9634	SUPAPA DE SIGURANTA Dn 50 / 80, #300	buc	1,000		
2	9677	DISPOZITIV DESCHIDERE RAPIDA 12 inch 300#	buc	1,000		
3	9097	MANOMETRU INDICATOR, RACORDARE LA PROCES: 1/2 INCH NPT	buc	5,000		
4	9678	INDICATOR TRECERE GODEVIL FL. 1 INCH PN 50	buc	2,000		
5	9679	MICROINTRERUPATOR DETECTIE DESCHIDERE USA	buc	1,000		
6	9096	PRESOSTAT RACORD LA PROCES 1/2 INCH NPT	buc	1,000		
7	9680	PRESOSTAT DIFERENTIAL RACORD LA PROCES 1/2 INCH NPT	buc	3,000		
8	9650	TRADUCTOR TEMPERATURA + TEACA DE PROTECTIE INOX	buc	2,000		

TOTAL:			lei		
TVA:			19,00 %	lei	
TOTAL cu TVA:				lei	

PROIECTANT,