

Antemasuratoare
Lista cu cantitati de lucrari pe categorii de lucrari

SECTIUNEA TEHNICA			
Nr.	Capitol de lucrari	U.M.	Cantitatea
0	1	2	3
1	CL12C1 - Scari, parapete, pasarele, podeste, contravinturi, pane cu zabrele, bare si constructii metalice de sustinere a utilajelor tehnologice sau platforme de deservire a agregatelor mari, pana la 0,150 T masa proprie prin sudura, cu inaltimea de pana la 35M inclusiv	tona	1,000
			material:
			manopera:
			utilaj:
			transport:
1.1	10105 - Procurare skid metalic pompe	kg	3.617,000
1.2	5822283 - Surub cap hexagonal grosolan M 20X 60 GR. 4.8 S 920	buc	2,000
1.3	5840601 - Piulite hexag.grosolane a m 20 GR. 5 S 922	buc	2,000
1.4	5882295 - Saiba prec.plata pentru met a m 22 OL 34 S 5200	kg	0,033
1.5	5900839 - Electrode sud.O.L.nealiat S 1125/2 E48T superextra 4	kg	1,750
1.6	5901340 - Electrode sud.O.L.slab aliat S 1125/2 E50B 4	kg	5,250
1.7	5904512 - Oxigen tehnic gazos imbuteliat stas 2031 clasa a	mc	1,500
1.8	7308164 - Carbura calciu tehnica (carbida) stas 102-63	kg	1,000
1.9	7399999 - Material marunt	%	2,000
1.10	27110 - Sudor electric	ora	34,310
1.11	19730 - Montator constructii metalice	ora	33,860
1.12	18111 - Lacatus constructii metalice	ora	6,970
1.13	3004 - Convertizor sudura(incl. cons.energie electrica)1-14KW	ora	7,000
2	AUT6729 - Macara pe pneuri 10-14,9tf \$	ORA	12,000
			material:
			manopera:
			utilaj:
			transport:
2.1	6729 - Macara pe pneuri 10-14,9 tf	ora	12,000
3	MDTA4624A1 - Montarea completa utilaj-65121003-macara pe pneuri de 0,15-0,199 mn(15-19,9tf)	buc	1,000
			material:
			manopera:
			utilaj:
			transport:
3.1	1001 - Cheltuieli pentru montare utilaje-mii lei	ora	40,572
4	MDTB4624A1 - Demontarea completa utilaj-65121003-macara pe pneuri de 0,15-0,199 mn(15-19,9tf)	buc	1,000
			material:
			manopera:
			utilaj:
			transport:
4.1	1002 - Cheltuieli pentru demontare utilaje-mii lei	ora	23,296

5	MDTC4624005 - Transport utilaj 5 km-65121003-macara pe pneuri de 0,15-0,199 mn(15-19,9tf)	buc	1,000
			material:
			manopera:
			utilaj:
			transport:
5.1	1003 - Cheltuieli pentru transport utilaje	ora	6,102
6	TRA04A50 - Transport rutier materiale semifabricate cu autoremorchere cu remorci treiler sub 20T pe dis.50 km.	tona	3,617
			material:
			manopera:
			utilaj:
			transport:
6.1	30172 - Transport rutier mater.semifabr. cu autoremorchere cu remorci treiler sub 20T pe dis.50 km.	tona	3,617
7	TRI1AA01F1 - Incarcarea materialelor, grupa a-grele si marunte,prin tran.pina la 10M rampa sau teren-auto cate	tona	3,617
			material:
			manopera:
			utilaj:
			transport:
7.1	20900 - Muncitor incarcare-descarcare materiale	ora	1,628
8	TRI1AA08F1 - Descarcarea materialelor,grupa a-grele si marunte prin transport pina la 10M auto-rampa,teren categ.	tona	3,617
			material:
			manopera:
			utilaj:
			transport:
8.1	20900 - Muncitor incarcare-descarcare materiale	ora	1,266
9	TRB22D3A - Manipulat materiale si elemente prefabricate cu macara pe pneuri amplasa in pozitie fixa sarcina < 0,500 T	tona	3,617
			material:
			manopera:
			utilaj:
			transport:
9.1	20650 - Muncitor de deservire pentru montajul in constructii	ora	1,230
9.2	6728 - Macara pe pneuri pina la 9,9tf	ora	0,410
10	IZD02C1 - Curatire rugina cu perie sirma a pieselor metalice parapete.balustrade	TONA	3,617
			material:
			manopera:
			utilaj:
			transport:
10.1	30110 - Vopsitor industrial	ora	13,368
11	IZD03A1 - Vopsirea cu pensula de mina cu vopsea de miniu pe conf si constr metal din profile cu gros 8-12M	TONA	3,617
			material:
			manopera:
			utilaj:
			transport:
11.1	6103294 - Vopsea minium de plumb V 351-3 ntr 90-80	kg	12,225
11.2	6200676 - White spirit rafinat tip a stas 44	kg	0,868
11.3	30110 - Vopsitor industrial	ora	5,968

12	IZD10A1 - Vopsirea anticoroziva cu pensula de mina a confectsi constr metal din profile intre 8-12 MM	TONA	3,617
			material:
			manopera:
			utilaj:
			transport:
12.1	6100814 - Grund miniu anticoroziv G.355-6 ni 1703-80	kg	14,106
12.2	9006109420 - Diluant ptr lacuri anticorozive D006-1 ni 1708-61 a1	kg	1,989
12.3	7306661 - Bumbac de sters	kg	3,527
12.4	6200676 - White spirit rafinat tip a stas 44	kg	7,053
12.5	30110 - Vopsitor industrial	ora	23,319
13	YC01 - Procurat vopsea anticoroziva grund 2K OCTAREP in doua straturi	kg	32,400
			material:
			manopera:
			utilaj:
			transport:
13.1	20019322 - Procurare mortar necontractil SIKA 314 sau echivalent	kg	1.049,760
13.2	200193221 - Procurat vopsea anticoroziva email epoxi 2K OCTAREP in trei straturi	kg	2.099,520

Proiectant,
S.C. RIA ENGINEERING & CONSULTING S.R.L.

