

Antemasuratoare
Lista cu cantitati de lucrari pe categorii de lucrari

SECTIUNEA TEHNICA			
Nr.	Capitol de lucrari	U.M.	Cantitatea
0	1	2	3
1	M1B10E1 - Electropompe, pompe vid, centrifuge supercentrifuge livrate asamblate 5,0-9,0 T.	tona	10,224
			material:
			manopera:
			utilaj:
			transport:
1.1	2917685 - Dulap fag lung tivit cls C GR = 50MM lun G = 2,50M s 8689	mc	0,051
1.2	3615911 - Tabla groasa 10X 1000 OL 37-1N s 437	kg	12,269
1.3	5820663 - Surub cap hexagonal grosolan M 10X 100 GR. 4.8 S 920	buc	20,448
1.4	5840443 - Piulite hexag.grosolane a m 10 GR. 5 S 922	buc	20,448
1.5	5901170 - Electrode sud.otel S 1125/2 E43.2 D=2,50MM inv. R1.2	kg	4,601
1.6	5904512 - Oxigen tehnic gazos imbuteliat stas 2031 clasa a	mc	1,840
1.7	6103294 - Vopsea minium de plumb V 351-3 ntr 90-80	kg	5,316
1.8	6200743 - Petrol distilat tip 0/200 np-nid 767	kg	4,090
1.9	6201527 - Uleiuri motoare aprind.scinteie nead. tip M 50 S 751	kg	3,067
1.10	6202612 - Unsori consistente de uz general U100 ca 4 S 562	kg	2,454
1.11	2955896 - Energie electrica la contor pentru lucrari de constr-montaj	kwh	23,004
1.12	7306661 - Bumbac de sters	kg	2,556
1.13	7308164 - Carbura calciu tehnica (carbid) stas 102-63	kg	1,227
1.14	18120 - Lacatus mecanic	ora	585,324
1.15	6728 - Macara pe pneuri pina la 9,9tf	ora	8,486
2	M7C03F1 - Revizia agregatelor rotative monoetajate cu greutate 4-32 T	tona	10,224
			material:
			manopera:
			utilaj:
			transport:
2.1	6002012 - Pinza pt.slef.usc.car.sil.nea.23X30 GR 16 foi S1582	buc	20,448
2.2	6108945 - Ulei de in sicativat U.001-13 stas 16-80	kg	2,556
2.3	6200535 - Benzina de extractie tip 80/120 S 45	l	15,336
2.4	6200743 - Petrol distilat tip 0/200 np-nid 767	kg	43,452
2.5	6202600 - Unsori consistente de uz general U 85 ca 3 S 562	kg	3,578
2.6	6202624 - Unsori pe baza de sapunuri pentru rulmenti 100ca3 S1608	kg	8,179
2.7	6622159 - Placa marsit M 100-500X3,0 MM S 3498	kg	12,269
2.8	7306661 - Bumbac de sters	kg	9,202
2.9	7308451 - Carton pentru izolatie electrica tip T1160G/mp 700X1000X1MM	kg	2,045
2.10	7323425 - Garnitura cinepa cu seu si impletit.ext.nr.02 D=10 MM	kg	7,668
2.11	7330399 - Mucava tip1 pasta bruna lemn 1400G/mp, satinata, coli	kg	15,336
2.12	7331135 - Oxid de zinc tehnic clitatea 2 continut minim 98,5 % stas 421 - 70	kg	0,409
2.13	18140 - Lacatus montaj agregate energetice	ora	366,019
2.14	6609 - Trolie electric 3,1-5tf	ora	3,987

2.15	6903 - Pod rulant electric 40,1-60tf	ora	20,755
3	M7C04B1 - Forte de munca pentru proba de punere in funct a agregrotative cu el mot cu putere peste 100 KW	buc	2,000
		material:	
		manopera:	
		utilaj:	
		transport:	
3.1	18140 - Lacatus montaj agregate energetice	ora	153,000
4	M7C05B1 - Uscarea electromotoarelor agregatelor rotative,cu puterea peste 100 KW	buc	2,000
		material:	
		manopera:	
		utilaj:	
		transport:	
4.1	4804492 - Cablu energie achpabi 0,6/ 1KV 3X 50 M s.4481 cl2	m	6,000
4.2	7304481 - Banda matase vegetala lacuita latimea 25 MM	m	40,000
4.3	7334450 - Placa din azbest	kg	6,400
4.4	18140 - Lacatus montaj agregate energetice	ora	277,600
5	AUT1106 - Ora pr macara pe pneuri cu brat cu zabrele 20,0-29,9 tf 1 schimb	ORA	16,000
		material:	
		manopera:	
		utilaj:	
		transport:	
5.1	8991106 - Ora pr macara pe pneuri cu brat cu zabrele 20,0-29,9 tf 1 schimb	ORA	16,000
6	TRI1AC04F3 - Incarcare materiale GR.C-ambalate,peste 100Kg deplas.prin purtare pina la 10M,frag.rampa,teren-auto ct	tona	10,224
		material:	
		manopera:	
		utilaj:	
		transport:	
6.1	20900 - Muncitor incarcare-descarcare materiale	ora	6,134
7	TRA04A50 - Transport rutier materiale semifabricate cu autoremorechere cu remorci treiler sub 20T pe dis.50 km.	tona	10,224
		material:	
		manopera:	
		utilaj:	
		transport:	
7.1	30172 - Transport rutier mater.semifabr. cu autoremorechere cu remorci treiler sub 20T pe dis.50 km.	tona	10,224
8	TRI1AC18F3 - Descarcare materiale GR.C-ambalate,peste 100Kg dep.prin transport pina la 10M,frag.auto-rampa,teren ctg.3	tona	10,224
		material:	
		manopera:	
		utilaj:	
		transport:	
8.1	20900 - Muncitor incarcare-descarcare materiale	ora	4,601
9	M1B10A1 - Electropompe, pompe vid, centrifuge supercentrifuge livrate asamblate 0,2-0,5 T.	tona	1,000
		material:	
		manopera:	
		utilaj:	
		transport:	
9.1	2917685 - Dulap fag lung tivit cls C GR = 50MM lun G = 2,50M s 8689	mc	0,005
9.2	3615911 - Tabla groasa 10X 1000 OL 37-1N s 437	kg	11,000
9.3	5820663 - Surub cap hexagonal grosolan M 10X 100 GR. 4.8 S 920	buc	9,000
9.4	5840443 - Piulite hexag.grosolane a m 10 GR. 5 S 922	buc	9,000
9.5	5901170 - Electrood sud.otel S 1125/2 E43.2 D=2,50MM inv. R1.2	kg	1,400

9.6	5904512 - Oxigen tehnic gazos imbuteliat stas 2031 clasa a	mc	1,440
9.7	6103294 - Vopsea minium de plumb V 351-3 ntr 90-80	kg	1,150
9.8	6200743 - Petrol distilat tip 0/200 np-nid 767	kg	0,400
9.9	6201527 - Uleiuri motoare aprind.scintele nead. tip M 50 S 751	kg	0,755
9.10	6202612 - Unsori consistente de uz general U100 ca 4 S 562	kg	0,400
9.11	2955896 - Energie electrica la contor pentru lucrari de constr-montaj	kwh	7,000
9.12	7306661 - Bumbac de sters	kg	0,250
9.13	7308164 - Carbura calciu tehnica (carbid) stas 102-63	kg	0,990
9.14	14300 - Electronist	ora	6,000
9.15	18120 - Lacatus mecanic	ora	72,750
9.16	6753 - Automacara cu brat cu zabrele 10- 14,9tf	ora	1,140
10	M7C03D1 - Revizia agregatelor rotative monoetajate cu greut 0,10-0,50 T	tona	1,000
		material:	
		manopera:	
		utilaj:	
		transport:	
10.1	6002012 - Pinza pt.slef.usc.car.sil.nea.23X30 GR 16 foi S1582	buc	6,000
10.2	6200535 - Benzina de extractie tip 80/120 S 45	l	3,000
10.3	6200743 - Petrol distilat tip 0/200 np-nid 767	kg	7,000
10.4	6202624 - Unsori pe baza de sapunuri pentru rulmenti 100ca3 S1608	kg	1,000
10.5	6622159 - Placa marsit M 100-500X3,0 MM S 3498	kg	2,500
10.6	7306661 - Bumbac de sters	kg	1,000
10.7	7323425 - Garnitura cinepa cu seu si impletit.ext.nr.02 D=10 MM	kg	1,500
10.8	7330399 - Mucava tip1 pasta bruna lemn 1400G/mp, satinata, coli	kg	3,000
10.9	18140 - Lacatus montaj agregate energetice	ora	190,300
11	M7C04A1 - Forte de munca pentru proba de punere in funct a agregrotative cu el mot cu putere P la 100 KW	buc	2,000
		material:	
		manopera:	
		utilaj:	
		transport:	
11.1	18140 - Lacatus montaj agregate energetice	ora	101,400
12	M7C05A1 - Uscarea electromotoarelor agregatelor rotative,cu puterea 10-100 KW	buc	2,000
		material:	
		manopera:	
		utilaj:	
		transport:	
12.1	4826646 - Conductor fcti -750 1X 25 S 526	m	4,000
12.2	7304481 - Banda matase vegetala lacuita latimea 25 MM	m	20,000
12.3	7334450 - Placa din azbest	kg	1,500
12.4	18140 - Lacatus montaj agregate energetice	ora	152,800
13	AUT1106 - Ora pr macara pe pneuri cu brat cu zabrele 20,0-29,9 tf 1 schimb	ORA	16,000
		material:	
		manopera:	
		utilaj:	
		transport:	
13.1	8991106 - Ora pr macara pe pneuri cu brat cu zabrele 20,0-29,9 tf 1 schimb	ORA	16,000

14	TRI1AC04F3 - Incarcare materiale GR.C-ambalate,peste 100Kg deplas.prin purtare pina la 10M,frag.rampa,teren-auto ct	tona	1,000
			material:
			manopera:
			utilaj:
			transport:
14.1	20900 - Muncitor incarcare-descarcare materiale	ora	0,600
15	TRA04A50 - Transport rutier materiale semifabricate cu autoremorchere cu remorci treiler sub 20T pe dis.50 km.	tona	1,000
			material:
			manopera:
			utilaj:
			transport:
15.1	30172 - Transport rutier mater.semifabr. cu autoremorchere cu remorci treiler sub 20T pe dis.50 km.	tona	1,000
16	TRI1AC18F3 - Descarcare materiale GR.C-ambalate,peste 100Kg dep.prin transport pina la 10M,frag.auto-rampa,teren ctg.3	tona	1,000
			material:
			manopera:
			utilaj:
			transport:
16.1	20900 - Muncitor incarcare-descarcare materiale	ora	0,450

Proiectant,
S.C. RIA ENGINEERING & CONSULTING S.R.L.

