

Antemasuratoare
Lista cu cantitati de lucrari pe categorii de lucrari

SECTIUNEA TEHNICA			
Nr.	Capitol de lucrari	U.M.	Cantitatea
0	1	2	3
1	M1A12C1 - Piese uzinate pentru echiparea recipient. livrate independent, montate prin sudura sau surub .D=100 MM	buc	4,000
			material:
			manopera:
			utilaj:
			transport:
1.1	5821760 - Surub cap hexagonal grosolan M 16X 70 GR. 4.8 S 920	buc	10,600
1.2	5822403 - Surub cap hexagonal grosolan M 20X 80 GR. 4.8 S 920	buc	10,600
1.3	5823299 - Surub cap hexagonal grosolan M 27X 100 GR. 4.8 S 920	buc	5,800
1.4	5840558 - Piulita hexagonala grosolana a m 16 GR. 5, S 922	buc	10,600
1.5	5840601 - Piulite hexag.grosolane a m 20 GR. 5 S 922	buc	10,600
1.6	5841083 - Piulita hexagonala uzuala S 926 OL 37 M 27	buc	5,800
1.7	5900578 - Electrode sud.O.L.nealiat S 1125/2 E42B 3,25	kg	2,120
1.8	5904512 - Oxigen tehnic gazos imbuteliat stas 2031 clasa a	mc	0,180
1.9	2955896 - Energie electrica la contor pentru lucrari de constr-montaj	kwh	14,000
1.10	6621959 - Placa marsit M 10-300X2,0 MM S 3498	kg	0,800
1.11	7308164 - Carbura calciu tehnica (carbid) stas 102-63	kg	0,140
1.12	27110 - Sudor electric	ora	8,480
1.13	18160 - Lacatus montaj utilaj industrial	ora	4,880
2	AUT1106 - Ora pr macara pe pneuri cu brat cu zabrele 20,0-29,9 tf 1 schimb	ORA	4,000
			material:
			manopera:
			utilaj:
			transport:
2.1	8991106 - Ora pr macara pe pneuri cu brat cu zabrele 20,0-29,9 tf 1 schimb	ORA	4,000
3	TR11AC04F3 - Incarcare materiale GR.C-ambalate, peste 100Kg deplas.prin purtare pina la 10M, frag.rampa, teren-auto ct	tona	0,280
			material:
			manopera:
			utilaj:
			transport:
3.1	20900 - Muncitor incarcare-descarcare materiale	ora	0,168
4	TRA04A50 - Transport rutier materiale semifabricate cu autoremorchere cu remorci treiler sub 20T pe dis.50 km.	tona	0,280
			material:
			manopera:
			utilaj:
			transport:
4.1	30172 - Transport rutier mater.semifabr. cu autoremorchere cu remorci treiler sub 20T pe dis.50 km.	tona	0,280
5	TR11AC18F3 - Descarcare materiale GR.C-ambalate, peste 100Kg dep.prin transport pina la 10M, frag.auto-rampa, teren ctg.3	tona	0,280
			material:
			manopera:
			utilaj:
			transport:
5.1	20900 - Muncitor incarcare-descarcare materiale	ora	0,126

Proiectant,
S.C. RIA ENGINEERING & CONSULTING S.R.L.

