

Antemasuratoare
Lista cu cantitati de lucrari pe categorii de lucrari

SECTIUNEA TEHNICA			
Nr.	Capitol de lucrari	U.M.	Cantitatea
0	1	2	3
1	M1107A1 - Robinet cu 3 cai cu ac,corp alama,racord G 1/2"	buc	10,000
			material:
			manopera:
			utilaj:
			transport:
1.1	4509951 - Robinet 3 cai cu ac tip R-3a nii 6954	buc	0,000
1.2	6103294 - Vopsea minium de plumb V 351-3 ntr 90-80	kg	0,020
1.3	6200573 - Benzina auto neetilata tip co/R 75 normala S 176	l	0,100
1.4	7306661 - Bumbac de sters	kg	0,010
1.5	7322940 - Fuior cinepa	kg	0,020
1.6	7344211 - Sapun de rufe tip 60% acizi grasi stas 189-59	kg	0,010
1.7	18160 - Lacatus montaj utilaj industrial	ora	1,720
1.8	19730 - Montator constructii metalice	ora	7,700
1	000056 - Robinet cu ac DN15 PN63 tip B2 316SS	buc.	10,000
2	M1107A1 - Robinet cu 3 cai cu ac,corp alama,racord G 1/2"	buc	6,000
			material:
			manopera:
			utilaj:
			transport:
2.1	4509951 - Robinet 3 cai cu ac tip R-3a nii 6954	buc	0,000
2.2	6103294 - Vopsea minium de plumb V 351-3 ntr 90-80	kg	0,012
2.3	6200573 - Benzina auto neetilata tip co/R 75 normala S 176	l	0,060
2.4	7306661 - Bumbac de sters	kg	0,006
2.5	7322940 - Fuior cinepa	kg	0,012
2.6	7344211 - Sapun de rufe tip 60% acizi grasi stas 189-59	kg	0,006
2.7	18160 - Lacatus montaj utilaj industrial	ora	1,032
2.8	19730 - Montator constructii metalice	ora	4,620
2	000057 - Robinet cu ac DN15 PN25 TIP B2 316SS	buc.	6,000
2	000058 - Conector tubing male 12mm OD x 1/2" NPT M 316SS	buc.	16,000
2	000059 - Tubing 12mm OD 315SS	m	8,000
2	000060 - Capac tubing 12mm 316SS	buc	16,000

3	GD08A1 - Capac bombat din tabla de otel sudat la tevi avind DN= 50 MM	buc	14,000
			material:
			manopera:
			utilaj:
			transport:
3.1	3606350 - Tabla groasa 5X 1250 OL 37-1N s 437	kg	5,740
3.2	5903207 - Sarma plina pt.sud.si inc.sub flux S10mn1 4	kg	1,120
3.3	5904512 - Oxigen tehnic gazos imbuteliat stas 2031 clasa a	mc	0,700
3.4	7308164 - Carbura calciu tehnica (carbid) stas 102-63	kg	0,420
3.5	17160 - Instalator sanitar	ora	16,240
4	ATD01B3 - Teava din ol montata prin insurubare pentru prot. cabl. electr. si a tevilor de impuls,cu dn: 2	m	49,000
			material:
			manopera:
			utilaj:
			transport:
4.1	3305724 - Teava inst.neagra fl+mf M - 50(2) OL 32 1 S 7656	m	49,735
4.2	4117095 - Curba fonta maleabila G1 S472 DN 50 2	buc	9,800
4.3	4120236 - Mufa fonta maleabila M2 S475 DN 50 2	buc	24,500
4.4	17130 - Instalator electrician	ora	16,071
4.5	17160 - Instalator sanitar	ora	3,400
4.6	17150 - Instalator incalzire + gaze	ora	19,599
4.7	14120 - Electrician automatizare	ora	3,528
4.8	27110 - Sudor electric	ora	4,802
5	ATD29B - Suporti, stelaje, constructii metalice din elemente prefabricate zincate	kg	14,000
			material:
			manopera:
			utilaj:
			transport:
5.1	12526 - Element de constr met zincate	kg	14,000
5.2	5900712 - Electrode sud.OL.nealiat S 1125/2 E44C 2,5	kg	0,700
5.3	18150 - Lacatus montaj masini electrice	ora	0,434
5.4	27110 - Sudor electric	ora	2,198
6	ACB12Q1 - Imbinare prin sudura electr. piese legatura executata la pozitie avand dn 1200	buc	56,000
			material:
			manopera:
			utilaj:
			transport:
6.1	5901261 - Electrode stas 1125/2 tip E51.5a1 1 dxi 5X450 MM	kg	235,816
6.2	20650 - Muncitor de deservire pentru montajul in constructii	ora	97,440
6.3	27110 - Sudor electric	ora	487,759
6.4	19740 - Montator conducte	ora	50,960
6.5	3006 - Grup termic de sudura 28-35KW	ora	322,000

7	ATD29B - Suporti, stelaje, constructii metalice din elemente prefabricate zincate	kg	56,000
			material:
			manopera:
			utilaj:
			transport:
7.1	12526 - Element de constr met zincate	kg	3.360,000
7.2	5900712 - Electrode sud.OL.nealiat S 1125/2 E44C 2,5	kg	2,800
7.3	18150 - Lacatus montaj masini electrice	ora	1,735
7.4	27110 - Sudor electric	ora	8,791
8	CK35B# - Dibluri din metal fixate in ziduri din beton armat	buc	56,000
			material:
			manopera:
			utilaj:
			transport:
8.1	10088 - Dibli si ghermele	buc	56,000
8.2	28100 - Tamplar	ora	11,200
8	000061 - Surub si piulita impamantare diam.10x100mm	buc.	56,000
9	TRA01A50 - Transportul rutier al materialelor,semifabricatelor cu autobasculanta pe dist.= 50 km. \$	tona	4,140
			material:
			manopera:
			utilaj:
			transport:
9.1	8888988 - Transportul rutier al materialelor,semifabricatelor cu autobasculanta pe dist.= 50 km.	tona	4,140
10	TR11AA04F1 - Incarcarea materialelor, grupa a-usoare si marunte,prin transport pina la 10M rampa,teren-auto categ	tona	4,140
			material:
			manopera:
			utilaj:
			transport:
10.1	20900 - Muncitor incarcare-descarcare materiale	ora	2,691
11	TR11AA08F1 - Descarcarea materialelor,grupa a-grele si marunte prin transport pina la 10M auto-rampa,teren categ.	tona	4,140
			material:
			manopera:
			utilaj:
			transport:
11.1	20900 - Muncitor incarcare-descarcare materiale	ora	1,449

Proiectant,
S.C. RIA ENGINEERING & CONSULTING S.R.L.

