

Antemasuratoare
Lista cu cantitati de lucrari pe categorii de lucrari

SECTIUNEA TEHNICA			
Nr.	Capitol de lucrari	U.M.	Cantitatea
0	1	2	3
1	M1J03C1 - Conducta otel carbon,montata prin sudura electrica cu convertizor de sudura,in instalatie tehnologice 150-400. MM.	tona	0,850
			material:
			manopera:
			utilaj:
			transport:
1.1	3605057 - <i>Tabla constr.mecanice S901 4 X1000X2000 OL37-1N</i>	kg	1,020
1.2	5822324 - <i>Surub cap hexagonal grosolan M 20X 65 GR. 4.8 S 920</i>	buc	40,800
1.3	5840601 - <i>Piulite hexag.grosolane a m 20 GR. 5 S 922</i>	buc	40,800
1.4	5901259 - <i>Electrod sud.otel S 1125/2 E43.2 2X350 inv.supert.</i>	kg	7,395
1.5	6001991 - <i>Pinza pentru slef.usc.car.sil.nea.23X30 GR 10 foi S1582</i>	buc	7,480
1.6	6002713 - <i>Disc abrazive nylon 300X22X8</i>	buc	0,850
1.7	6202612 - <i>Unori consistente de uz general U100 ca 4 S 562</i>	kg	0,272
1.8	2955896 - <i>Energie electrica la contor pentru lucrari de constr-montaj</i>	kwh	17,340
1.9	6202806 - <i>Apa industriala in cisterne pentru lucrari de drumuri si terasamente</i>	mc	0,510
1.10	6621959 - <i>Placa marsit M 10-300X2,0 MM S 3498</i>	kg	2,550
1.11	7306661 - <i>Bumbac de sters</i>	kg	0,212
1.12	18120 - <i>Lacatus mecanic</i>	ora	58,373
1.13	27110 - <i>Sudor electric</i>	ora	20,475
1.14	19740 - <i>Montator conducte</i>	ora	2,759
1.15	18111 - <i>Lacatus constructii metalice</i>	ora	0,073
1.16	27120 - <i>Sudor gaze</i>	ora	0,073
1.17	2505 - <i>Electrocompres.mobil de joasa pres.10 - 20 MC/min</i>	ora	0,323
1.18	3004 - <i>Convertizor sudura(incl. cons.energie electrica)1-14KW</i>	ora	13,005
1.19	3304 - <i>Electropompa apa monoetaj.de joasa pres. 15-30 KW</i>	ora	0,391
1	563220 - <i>Gara de lansare godevil</i>	buc	1,000
2	AUT1106 - <i>Ora pr macara pe pneuri cu brat cu zabrele 20,0-29,9 tf 1 schimb</i>	ORA	16,000
			material:
			manopera:
			utilaj:
			transport:
2.1	8991106 - <i>Ora pr macara pe pneuri cu brat cu zabrele 20,0-29,9 tf 1 schimb</i>	ORA	16,000

3	TRI1AC04F3 - Incarcare materiale GR.C-ambalate,peste 100Kg deplas.prin purtare pina la 10M,frag.rampa,teren-auto ct	tona	0,850
			material:
			manopera:
			utilaj:
			transport:
3.1	20900 - Muncitor incarcare-descarcare materiale	ora	0,510
4	TRA04A50 - Transport rutier materiale semifabricate cu autoremorchere cu remorci treiler sub 20T pe dis.50 km.	tona	0,850
			material:
			manopera:
			utilaj:
			transport:
4.1	30172 - Transport rutier mater.semifabr. cu autoremorchere cu remorci treiler sub 20T pe dis.50 km.	tona	0,850
5	TRI1AC18F3 - Descarcare materiale GR.C-ambalate,peste 100Kg dep.prin transport pina la 10M,frag.auto-rampa,teren ctg.3	tona	0,850
			material:
			manopera:
			utilaj:
			transport:
5.1	20900 - Muncitor incarcare-descarcare materiale	ora	0,382
6	M1J03B1 - Conducta otel carbon,montata prin sudura electrica cu convertizor de sudura,in instalatie tehnologice 80-150 MM.	tona	0,650
			material:
			manopera:
			utilaj:
			transport:
6.1	3605057 - Tabla constr.mecanice S901 4 X1000X2000 OL37-1N	kg	0,780
6.2	5821708 - Surub cap hexagonal grosolan M 16X 60 GR. 4.8 S 920	buc	48,750
6.3	5840558 - Piulita hexagonala grosolana a m 16 GR. 5, S 922	buc	48,750
6.4	5901259 - Electrode sud.otel S 1125/2 E43.2 2X350 inv.supert.	kg	6,240
6.5	6001991 - Pinza pentru slef.usc.car.sil.nea.23X30 GR 10 foi S1582	buc	6,110
6.6	6002713 - Disc abrazive nylon 300X22X8	buc	0,650
6.7	6202612 - Unsoare consistente de uz general U100 ca 4 S 562	kg	0,208
6.8	2955896 - Energie electrica la contor pentru lucrari de constr-montaj	kwh	14,300
6.9	6202806 - Apa industriala in cisterne pentru lucrari de drumuri si terasamente	mc	0,260
6.10	6621959 - Placa marsit M 10-300X2,0 MM S 3498	kg	3,640
6.11	7306661 - Bumbac de sters	kg	0,162
6.12	18120 - Lacatus mecanic	ora	95,634
6.13	27110 - Sudor electric	ora	36,985
6.14	19740 - Montator conducte	ora	7,377
6.15	18111 - Lacatus constructii metalice	ora	0,146
6.16	27120 - Sudor gaze	ora	0,146
6.17	2505 - Electrocompres.mobil de joasa pres.10 - 20 MC/min	ora	0,897

6.18	3004 - Convertizor sudura(incl. cons.energie electrica)1-14KW	ora	27,846
6.19	3304 - Electropompa apa monoetaj,de joasa pres. 15-30 KW	ora	1,046
6	563230 - Gara de primire godevil	buc	1,000
7	AUT1106 - Ora pr macara pe pneuri cu brat cu zabrele 20,0-29,9 tf 1 schimb	ORA	16,000
		material:	
		manopera:	
		utilaj:	
		transport:	
7.1	8991106 - Ora pr macara pe pneuri cu brat cu zabrele 20,0-29,9 tf 1 schimb	ORA	16,000
8	TRI1AC04F3 - Incarcare materiale GR.C-ambalate,peste 100Kg deplas.prin purtare pina la 10M,frag.rampa,teren-auto ct	tona	0,650
		material:	
		manopera:	
		utilaj:	
		transport:	
8.1	20900 - Muncitor incarcare-descarcare materiale	ora	0,390
9	TRA04A50 - Transport rutier materiale semifabricate cu autoremorchere cu remorci treiler sub 20T pe dis.50 km.	tona	0,650
		material:	
		manopera:	
		utilaj:	
		transport:	
9.1	30172 - Transport rutier mater.semifabr. cu autoremorchere cu remorci treiler sub 20T pe dis.50 km.	tona	0,650
10	TRI1AC18F3 - Descarcare materiale GR.C-ambalate,peste 100Kg dep.prin transport pina la 10M,frag.auto-rampa,teren ctg.3	tona	0,650
		material:	
		manopera:	
		utilaj:	
		transport:	
10.1	20900 - Muncitor incarcare-descarcare materiale	ora	0,292

Proiectant,
S.C. RIA ENGINEERING & CONSULTING S.R.L.

