

Anexa explicitare norme

Nr.	Simbol	Denumirea resursei	Tip	U.M.	Cantitate	Pretul unitar (fara TVA) - Lei -	Valoarea (fara TVA) - Lei -
0	1	2	3	4	5	6	7 = 5 X 6

W1M23XD1-01							
Cablu de energie electrica de 20KV monofazat 150mm pozat mecanic - pentru cablu tras manual prin tub de protectie							
1	12220	Cabluri electr de 6-110 KV	Lista	m	3,075.000		
1.1	4807846	Cablu energie a2ysy 12/20 KV 1X150 str.E 535/8	Mat	%	100.000		
2	6716948	Folie de pvc G = 0,8 ntr 9001-80	Mat	kg	100.000		
3	8000277	Material marunt	Mat	%	1.000		
4	14100	Electrician	Man	ora	960.000		
TOTAL W1M23XD1-01						km	

W1M26XA							
Cap terminal uscat pentru cabluri de 20KV de interior							
1	90407	Set mat.pt.un cap terminal de int.(proc.separat)-	Lista	-	3.000		
2	8000277	Material marunt	Mat %	%	1.000		
3	14100	Electrician	Man	ora	11.600		
TOTAL W1M26XA						buc	

W1SD09H%							
Conector electric de 400 a, 150 MM2							
1	2955896	Energie electrica la contor pentru lucrari de constr-montaj	Mat	kwh	22.000		
2	14180	Electrician post trafo	Man	ora	0.450		
TOTAL W1SD09H%						buc	

W1M23XA1-01							
Cablu de energie electrica de 20KV monofazat 150mm pozat manual - pentru cablu tras manual prin tub de protectie							
1	12220	Cabluri electr de 6-110 KV	Lista	m	3,075.000		
1.1	4807846	Cablu energie a2ysy 12/20 KV 1X150 str.E 535/8	Mat	%	100.000		
2	6716948	Folie de pvc G = 0,8 ntr 9001-80	Mat	kg	0.000		
3	8000277	Material marunt	Mat	%	1.000		
4	14100	Electrician	Man	ora	1,440.000		
TOTAL W1M23XA1-01						km	