

**LISTA DE MATERIALE  
PROIECTARE REZERVOR PENTRU APA P.S.I.  
– RAMPA INCARCARE TITEI BILED**

01	Emis pentru utilizare	14.12.2021	Birlodeanu C.	Mircia R.	Danilov B.	
00	Emis pentru comentarii	02.12.2021	Birlodeanu C.	Mircia R.	Danilov B.	
Rev/ Rev.	Denumireamodificarii/Change description	Data/Date	Pr Spec / Consultant	Verificat/Checked	Aprobat / Approved	
<b>ROENGG CONSULTING</b> Str. Sinaii, Bloc 10C2 Ap 22 Ploiesti contact@roengg.com	<b>S.C. CONPET S.A.</b> Strada Anul 1848 nr 1-3, cod postal 100559, Ploiesti, Prahova, ROMANIA	Nr. proiect / Project no.	Nr. desen / Drawing no.		Faza/Phase	Rev/Rev
		<b>10232020</b>	<b>RNG-LM-12-201</b>		<b>PT+D.D.E</b>	<b>01</b>
Scara/Scale	Denumire document/Document name					
-	LISTA DE MATERIALE					
Pag1/2						

Nr. crt.	Denumire	Specificatie	Cantitate	Observatii
0.	1	2	3	4
1.	Sapatura	-	98 m <sup>3</sup>	
2.	Umplutura compactata material local	-	58 m <sup>3</sup>	
3.	Strat rupere capilaritate	-	6.5 m <sup>3</sup>	
4.	Folie PVC	-	64 m <sup>2</sup>	
5.	Cofraj	-	23 m <sup>2</sup>	
6.	Beton simplu C12/15	-	25.5 m <sup>3</sup>	
7.	Beton armat C25/30	-	41.5 m <sup>3</sup>	
8.	Armatura PC52	-	4165kg	
9.	Buloane de ancorare rezervor M20	-	72 buc.	Va fi confirmat de producatorul rezervorului