

## LISTA MATERIALE LUCRARI CIVILE

03	Emis pentru utilizare		06.05.2022	Birlodeanu C.	State G.	Dobleaga S.						
02	Emis pentru utilizare		18.04.2022	Birlodeanu C.	State G.	Dobleaga S.						
01	Emis pentru utilizare		15.03.2022	Birlodeanu C.	State G.	Dobleaga S.						
Rev. / Rev.	Denumirea modificarii / Change description		Data / Date	Pr. Spec. / Consultant	Verificat / Checked	Aprobat / Approved						
ROENGG CONSULTING Str. Sinaii, Bloc 10C2 Ap 22 Ploiesti contact@roengg.com			CONPET S.A. Romania Str. Anul 1848 nr.1-3 Ploiesti		Nr. proiect / Project no.		Nr. desen / Drawing no.		Faza / Phase		Rev. / Rev.	
					10202020		RNG-LM-12-001		PT + DDE		03	
Scara / Scale			Denumire document / Document name									
-			LISTA MATERIALE LUCRARI CIVILE									
Pag. 1/3												

Nr. Crt.	Echipament / Material	Unitate de masura	Cantitate	Observatii
<b>1. Fundatii grup pompe titei – RNG-DM-12-001</b>				
1.	Beton simplu – C12/15 Beton armat – C25/30	m <sup>3</sup> m <sup>3</sup>	1.90 23.50	
2.	Armatura PC52	kg	2128	
3.	Cofraj	m <sup>2</sup>	45	
4.	Elemente inglobate in fundatii – carcasa buloane	kg	199	
5.	Profile laminate (inclusiv gratar meiser 30x3 sau similar)	kg	25	
6.	Mortar de panta	m <sup>3</sup>	1.2	
7.	Mortar Sika 314 sau similar	m <sup>3</sup>	0.5	
<b>2. Fundatii copertina pentru grupul de pompe titei - RNG-DM-12-002</b>				
8.	Beton simplu – C12/15 Beton armat – C25/30	m <sup>3</sup> m <sup>3</sup>	3.8 18.9	
9.	Armatura PC52	kg	1980	
10.	Cofraj	m <sup>2</sup>	41	
11.	Elemente inglobate in fundatii – carcasa buloane	kg	186	
12.	Sapatura	m <sup>3</sup>	88	
13.	Umplutura compactata 95 %Proctor	m <sup>3</sup>	50	
<b>3. Structura metalica copertina pentru grupul de pompe titei - RNG-DM-12-003</b>				
14.	Structura metalica (profile laminate UPN, Teava 100x100x5; Hea 180, tabla 8;12;15;20mm)	kg	3215	
15.	Suruburi M12;M20 gr 8.8	kg	38	
16.	Tabla invelitoare	m <sup>2</sup>	71.5	
17.	Jgheab	m	9.35	
18.	Burlan	m	3	
<b>4. Fundatii suportu conducta- RNG-DM-12-004</b>				
19.	Beton simplu – C12/15 Beton armat – C25/30	m <sup>3</sup> m <sup>3</sup>	0.50 1.7	
20.	Armatura PC52	kg	156	
21.	Cofraj	m <sup>2</sup>	1.8	
22.	Mortar Sika 314 sau similar	m <sup>3</sup>	0.2	
23.	Amcore chimice HIT RE500 SD sau similar	buc.	8	
24.	Sapatura	m <sup>3</sup>	10.5	

Proiect nr. / Project no.	Nr. document / Document no.	Denumire document / Document name	Rev. / Rev.
<b>10202020</b>	<b>RNG-LM-12-001</b>	<b>LISTA MATERIALE LUCRARI CIVILE</b>	<b>03</b>

25.	Umplutura compactata 95% Proctor	m <sup>3</sup>	8	
<b>5. Refacere cuva robinete- RNG-DM-12-005</b>				
26.	Beton armat – C25/30	m <sup>3</sup>	1.5	
27.	Armatura	kg	122	
28.	Mortar de panta	m <sup>3</sup>	0.6	
29.	Cofraj	m <sup>2</sup>	6.5	
<b>6. Dala si suport metalic tablouri electrice si AMC- RNG-DM-12-005</b>				
30.	Beton armat – C25/30	m <sup>3</sup>	1.53	
31.	Folie PVC	m <sup>2</sup>	5.5	
32.	Armatura PC52	kg	125	
33.	Cofraj	m <sup>2</sup>	2.85	
34.	Sapatura	m <sup>3</sup>	1.0	
35.	Umplutura	m <sup>3</sup>	0.2	
36.	Amcore chimice HIT RE500 SD M16x190 sau similar	buc.	16	
37.	Structura metalica (profile laminate UPN80, Teava 100x100x5; tabla 5;10;12)	kg	465	
<b>6. Zona pavata cu dale 0.8x0.8m - RNG-PL-12-001-02</b>				
38.	Beton armat – C25/30	m <sup>3</sup>	3.52	
39.	Armatura PC52	kg	160	
40.	Cofraj	m <sup>2</sup>	17.6	
41.	Nisip	m <sup>2</sup>	13	

Proiect nr. / Project no.	Nr. document / Document no.	Denumire document / Document name	Rev. / Rev.
<b>10202020</b>	<b>RNG-LM-12-001</b>	<b>LISTA MATERIALE LUCRARI CIVILE</b>	<b>03</b>