

LISTA DE MATERIALE AMC

02						
01	Emis pentru construire	12.04.2022	Trifan O.	Danilov B	Dobleaga S.	
00	Emis pentru comentarii	26.02.2021	Trifan O.	Corbu O	Danilov B	
Rev. / Rev.	Denumirea modificarii / Change description	Data / Date	Pr. Spec. / Consultant	Verificat / Checked	Aprobat / Approved	
ROENGG CONSULTING Ploiesti contact@roengg.com	S.C. CONPET S.A. Strada Anul 1848 nr 1-3, cod postal 100559, Ploiesti, Prahova, ROMANIA	Nr. proiect / Project no.		Nr. desen / Drawing no.		Rev. / Rev.
		10202020		RNG-LM-16-002		01
Scara / Scale		Denumire document / Document name				
-		LISTA DE MATERIALE AMC				
Pag. 1/2						

Nr. Crt.	Echipament / Material	Cantitate		Observatii
1.	Manometre, ansamblu robinete DBB	2	buc.	Conform Specificatie tehnica 10202020-RNG-ST-16-002
2.	Manometre, ansamblu robinete SBB	2	buc.	Conform Specificatie tehnica 10202020-RNG-ST-16-002
3.	Intrerupatoare de debit, cu furca vibratoare	2	buc.	Conform Specificatie tehnica 10202020-RNG-ST-16-004
4.	Traductor de presiune, ansamblu robinete DBB	1	buc.	Conform Specificatie tehnica 10202020-RNG-ST-16-001
5.	Debitmetru Coriolis	1	buc.	Conform Specificatie tehnica 10202020-RNG-ST-16-003
6.	Sistem comanda si control cu trimitere la distanta tip RTU in carcasa metalica, Modem GSM, multi-port firewall	1	buc.	Conform Specificatie tehnica 10202020-RNG-ST-16-006
7.	Cablu tip 1	310	m.	Conform Specificatie tehnica 10202020-RNG-ST-16-005
8.	Cablu tip 2	85	m.	Conform Specificatie tehnica 10202020-RNG-ST-16-005
9.	Cablu tip 3	165	m.	Conform Specificatie tehnica 10202020-RNG-ST-16-005
10.	Jgheab metalic perforat, OLZN 50x55x1,5 mm., cu capac, pentru incarcari normale, inclusiv piese de legatura	10	m.	- pentru instalare la exterior
11.	Conductor impamantare pentru instrumente (cablu VPLY) 10 mm ² – galben / verde	10	m.	
12.	Conector cu filet exterior 2/2/1	6	buc.	1/2" NPT-M x 1/2" tubing
13.	Tubing purjare 0.6/0.6/0.3	2	m.	1/2"
14.				
15.				
16.				
17.				
18.				
19.				
20.				
21.				
22.				
23.				
24.				
25.				