

**LISTA DE MATERIALE
PROIECTARE REZERVOR PENTRU APA P.S.I.
– RAMPA INCARCARE TITEI BILED**

02	Emis pentru utilizare	21.12.2022	Birlodeanu C.	Danilov B.	Danilov B.	
01	Emis pentru utilizare	14.12.2021	Birlodeanu C.	Mircia R.	Danilov B.	
00	Emis pentru comentarii	02.12.2021	Birlodeanu C.	Mircia R.	Danilov B.	
Rev/ Rev.	Denumireamodificarii/Change description	Data/Date	Pr Spec / Consultant	Verificat/Checked	Aprobat / Approved	
ROENGG CONSULTING Str. Sinaii, Bloc 10C2 Ap 22 Ploiesti contact@roengg.com	S.C. CONPET S.A. Strada Anul 1848 nr 1-3, cod postal 100559, Ploiesti, Prahova, ROMANIA	Nr. proiect / Project no.		Nr. desen / Drawing no.		
		10232020		RNG-LM-12-201		
		Faza/Phase				Rev/Rev
		PT+D.D.E				02
Scara/Scale		Denumire document/Document name				
-		LISTA DE MATERIALE				
Pag1/2						

Nr. crt.	Denumire	Specificatie	Cantitate	Observatii
0.	1	2	3	4
1.	Sapatura	-	98 m ³	
2.	Umplutura compactata material local	-	58 m ³	
3.	Strat rupere capilaritate	-	6.5 m ³	
4.	Folie PVC	-	64 m ²	
5.	Cofraj	-	66 m ²	
6.	Beton simplu C12/15	-	26.5 m ³	
7.	Beton armat C25/30 sau C30/37	-	49.5 m ³	
8.	Aditiv impermeabilizare min. P12	-	200 kg	
9.	Armatura PC52	-	4965kg	
10.	Buloane de ancorare rezervor rez M20	-	72 buc.	Va fi confirmat de producatorul rezervorului