

```

=====
= NR. SIMBOL ART.   CANTITATE      UM      PU MAT   VAL MAT =
=   D E N U M I R E      A R T I C O L      PU MAN   VAL MAN =
=                                     PU UTI   VAL UTI =
=                                     PU TRA   VAL TRA =
= SPOR MAT MAN UTI      GR./UA    GR.TOT.      T O T A L =
=====
001  CE14A1    [ 4] M      1.000      1.67      1.67
BURLANE DIN TABLA ZINCATA DE 0,5MM      0.69      0.69
CONFECTIONATE PE SANTIER ROTUNDE CU D=      0.00      0.00
15,4CM      0.00      0.00
0.003      0 Total=      2.36

```

```

-----
Reteta normei:  CE14A1    [ 4]      P.U.      Consum U.M.
3271522 PROCURARE BURLANE DIN TABLA LINDAB      1.00      1.00000 M
5904770 ALIAJ DE LIPIT STANIU-PLUMB LP30      $      1.00      0.07000 KG
6311982 BRATARI DIN OTEL ZINCAT PENTRU BURLANE (SEMIROTUNDE SA~      1.00      0.60000 BUC.
13100  TINICHIGIU SANT.      1.00      0.69000 ORA
-----

```

```

002  CE13C1    [ 2] M      1.000      3.48      3.48
JGHEABURI MARO VOPSITE IN CAMP      0.36      0.36
ELECTROSTATIC INCLUSIV CARLIGE ,SORTURI      0.00      0.00
0.00      0.00
0.009      0 Total=      3.83

```

```

-----
Reteta normei:  CE13C1    [ 2]      P.U.      Consum U.M.
6200527 JGHEABURI MARO VOPSITE IN CAMP ELECTROSTATIC      1.00      1.50000 M
2000030 OTEL BETON PROFIL NETED OB37      STAS 438 D= 6MM      $      1.00      0.23000 KG
6311231 CIRLIGE DIN OTEL ZINCATE PENTRU JGHEABURI      1.00      1.50000 BUC.
3700390 BANDA DIN OTEL LAMINAT LA CALD S908 3 X 30 OL37-1N      1.00      0.24500 KG
13100  TINICHIGIU SANT.      1.00      0.36000 ORA
-----

```

```

003  IZF04A1   [ 3] MP.      1.000      0.00      0.00
MONTAT FOLIE PVC      0.04      0.04
0.00      0.00
0.00      0.00
0.000      0 Total=      0.04

```

```

-----
Reteta normei:  IZF04A1   [ 3]      P.U.      Consum U.M.
12200  IZOLATOR HIDROFUG      1.00      0.04034 ORA
-----

```

```

004  EA02B3    [ 3] M      1.000      0.00      0.00
TUB PVC CU D=50MM MONTAT IN PAMANT      0.65      0.65
0.00      0.00
0.00      0.00
0.000      0 Total=      0.65

```

```

-----
Reteta normei:  EA02B3    [ 3]      P.U.      Consum U.M.

```

=====

11500	INSTALATOR ELECTRICIAN		1.00	0.65000	ORA
-------	------------------------	--	------	---------	-----

005	EA06C1	[4] M	1.000	1.36	1.36
	TEAVA OTEL PENTRU INSTALATII SUDATA,			1.03	1.03
	ZINCATA MONTATA INGROPAT IN PARDOSEALA D			0.00	0.00
	=2 TO			0.00	0.00
		0.005	0 Total=	2.39	

Reteta normei:	EA06C1	[4]		P.U.	Consum U.M.
4117095	CURBA FONTA MALEABILA G1		S472 DN 50 2 TOLI ~	1.00	0.35000 BUC.
3805372	SIRMA MOALE ZINCATA D= 2	OL32	S 889 \$	1.00	0.00400 KG
3306003	TEAVA INSTALATII ZINCATA NEFILETATA UII-	50(2	) OL ~	1.00	1.01000 M
11500	INSTALATOR ELECTRICIAN			1.00	1.03000 ORA

006	EA10D2	[2] M	1.000	0.15	0.15
	TEAVA PVC TIP U MONTATA INGROPAT IN			0.60	0.60
	PARDOSEALA CU D=90MM			0.00	0.00
				0.00	0.00
		0.000	0 Total=	0.75	

Reteta normei:	EA10D2	[2]		P.U.	Consum U.M.
6110467	CODEZ 100 ADEZIV		NII 4721-76\$	1.00	0.01700 KG
7317232	DICLORETAN	CS. 17/73	\$	1.00	0.01400 KG
6001965	PINZA PENTRU SLEFUIT USCATA CARBURA SILICIU NEARMATA 23~			1.00	0.10000 BUC.
6200573	BENZINA AUTO NEETILATA TIP CO/R 75 NORMALA		S 176 \$	1.00	0.01400 L
3805372	SIRMA MOALE ZINCATA D= 2	OL32	S 889 \$	1.00	0.00600 KG
7306661	BUMBAC DE STERS		\$	1.00	0.00100 KG
11500	INSTALATOR ELECTRICIAN			1.00	0.60000 ORA

007	EA02B3	[3] M	1.000	0.00	0.00
	TUB PVC CU D=50MM MONTAT IN PAMANT			0.65	0.65
				0.00	0.00
				0.00	0.00
		0.000	0 Total=	0.65	

Reteta normei:	EA02B3	[3]		P.U.	Consum U.M.
11500	INSTALATOR ELECTRICIAN			1.00	0.65000 ORA

008	ATD13A	[3] M	1.000	0.00	0.00
	CABLU MASURA, CDA, SEMNALIZARE POZAT PE			0.47	0.47
	ZID, POD, CU: PINA LA 10 FIRE CONDUCTOARE			0.00	0.00
	DE 1,5-2,5 MMP			0.00	0.00
		0.000	0 Total=	0.47	

Reteta normei:	ATD13A	[3]		P.U.	Consum U.M.
0012510	CABLURI MASURA C-DA SEMNALIZARE				1.01500
11500	INSTALATOR ELECTRICIAN			1.00	0.29596 ORA
11611	INSTALATOR SANITAR CAT.1			1.00	0.06939 ORA
20500	ELECTRICIAN AUTOMATIZARE			1.00	0.10498 ORA

009	IZI07C1	[1] MP.	1.000	0.05	0.05
	PROTEC TERMOIZ LA CONDUCTE SI APARATE CU			0.24	0.24
	TABLA DE 05 MM CU CIRC PESTE TERMOIZ 090			0.00	0.00
	-1,6 M CONF			0.00	0.00
		0.000	0 Total=		0.28

Reteta normei:	IZI07C1	[1]		P.U.	Consum U.M.
0011242	TABLA NEAGRA,ZINCATA,ALUMIN.PROTECTIE				4.00000
6202741	ENERGIE ELECTRICA LA CONTOR PENTRU LUCRARI DE CONSTR-MO~			1.00	0.04900 KWH.
13100	TINICHIGIU SANT.			1.00	0.23584 ORA

010	IZI07C2	[1] MP.	1.000	7.00	7.00
	PROTEC TERMOIZ LA CONDUCTE SI APARATE CU			0.68	0.68
	TABLA DE 05 MM CU CIRC PESTE TERMOIZ 090			0.00	0.00
	-1,6 M MONTARE			0.00	0.00
		0.000	0 Total=		7.68

Reteta normei:	IZI07C2	[1]		P.U.	Consum U.M.
5828768	SURUB CILINDRIC+A FILETAT N.1636		M 4 X 15	1.00	7.00000 BUC.
13100	TINICHIGIU SANT.			1.00	0.67722 ORA

011	CB47A1	[4] M.C.	1.000	0.00	0.00
	MONTAREA SI DEMONTARE SCHELEI MET			0.55	0.55
	TUBULARE PT LUCRARI PE SUPRAFETE			0.00	0.00
	VERTICALE H<30,0M			0.00	0.00
		0.001	0 Total=		0.55

Reteta normei:	CB47A1	[4]		P.U.	Consum U.M.
2918639	DULAPI FAG IMPREGNATI BALOTATI LUNGIME=1,8- 5M CLASA A			1.00	0.00080 M.C.
2925412	PLACA PFL DURE STANDARD CALII 1FATA NETEDA 1830X1700X6,~			1.00	0.00012 M.C.
5886942	CUIE CU CAP CONIC TIP A1 3 X 70 OL34 S 2111\$			1.00	0.00300 KG
10741	DULGHER CONSTRUCTII CAT.4			1.00	0.55000 ORA

012	M1L64A1	[1] BUC.	1.000	0.14	0.14
	CONTROLUL CU LICHIDE PENETRANTE A SUD LA			3.20	3.20
	COND IN RAMIFICATIE COND AVIND DN PINA			0.60	0.60
	LA 160MM			0.00	0.00
		0.000	0 Total=		3.94

Reteta normei:	M1L64A1	[1]		P.U.	Consum U.M.
7317233	SET LP			1.00	0.06000 BUC.
7306661	BUMBAC DE STERS		\$	1.00	0.08000 KG
25021	MONTATOR CONDUCTE CAT.2			1.00	1.00000 ORA
21531	LACATUS MONTAJ UTILAJ INDUSTRIAL CAT.3			1.00	0.60000 ORA
25051	MONTATOR CONDUCTE CAT.5			1.00	1.00000 ORA
21521	LACATUS MONTAJ UTILAJ INDUSTRIAL CAT.2			1.00	0.60000 ORA
8992504	ELECTROCOMPRES.MOBIL DE JOASA PRES. 4,0-5,9 MC/MIN			1.00	0.30000 ORA
8995704	PLATFORMA RIDICATOARE CU BRATE TIP PRB-15 PE AUTO 5T			1.00	0.30000 ORA