

Formularul F3

Obiectivul: 0309 45330000 RETEA TITEI CONPET URLATI -
ORZOAIA
Obiectul: 0001 45330000 CONPET URLATI - ORZOAIA
Lista cu cantitatile de lucrari
Deviz oferta 309001 VARIANTA I

Categoriza de lucrari: 0131

```
=====
= NR. SIMBOL ART.  CANTITATE      UM          PU MAT  VAL MAT  =
=   D E N U M I R E                PU MAN  VAL MAN  =
=                                A R T I C O L  PU UTI  VAL UTI  =
=                                PU TRA   VAL TRA  =
= SPOR MAT MAN UTI      GR./UA   GR.TOT.      T O T A L  =
=====
```

001 TSH01A1 100 MP. 29.400
DEGAJAREA TERENULUI DE CORPURI STRAINE

002 TSA02G1 M.C. 453.480
SAP.MAN.IN SPATII LIMIT.SUB 1M CU TALUZ
VERT.NESPR.IN PAM.COEZ.MIJ.SI F.COEZ.
ADINC.<1,5M T.F.TAR

003 TSC02C1 100 MC. 10.580
SAPATURA CU EXCAVAT.PE PNEURI 0,21-0,39
MC PAMINT UMIDIT.NATUR.DISC AUT.TER.CAT.
1

004 TSC02C1 100 MC. 1.830
SAPATURA CU EXCAVAT.PE PNEURI 0,21-0,39
MC PAMINT UMIDIT.NATUR.DISC AUT.TER.CAT.
1- GROAPA DE POZITIE

005 GD11A1# M.C. 307.670
STRAT DE NISIP PENTRU PROTEJARE CONDUCTE
PE

006 TSD01C1 M.C. 1444.720
IMPRASTIEREA CU LOPATA A PAMINT.AFINAT,
STRAT UNIFORM 10-30CM.GROS CU SFARIM.
BULG.TEREN TARE

007 TSD04B1 M.C. 1203.930
COMPACTAREA CU MAI.DE MINA A UMPLUT.
EXECUT.PE STRAT.CU UDAREA FIEC.STRAT DE
10CM GROS.T.COEZIV

008 TRI1AA01C1 TONA 41.500
INCARCAREA MATERIALELOR,GRUPA A-GRELE SI
MARUNTE,PRIN ARUNCARE RAMPA SAU TEREN-
AUTO CATEG.1

009 TRA01A10P TONA 2695.250
TRANSPORTUL RUTIER AL PAMINTULUI SAU
MOLOZULUI CU AUTOBASCULANTA DIST.=10 KM

=====

010 GA09C1	M	7.000
------------	---	-------

ASIM- FORAJ ORIZONTAL DIRIJAT DN 400 MM

011 TSF01A1	MP.	378.240
-------------	-----	---------

SPRIJIN.DE MALURI CU DULAPI DE FAG ASEZ.
ORIZ.LAT.INTRE MAL.<1,5M,ADIN.0,0-2M,0,0
-0,2M INTRE DULA

012 MDTC4641100	BUC.	1.000
-----------------	------	-------

TRANSPORT UTILAJ 100KM-65123003-
AUTOMACARA 0,045-0,059MN,H.MAX.6,5M,DES.
MAX.5,5M,MOMENT MAX.15TF

013 TSH05A1	MP.	2940.000
-------------	-----	----------

ASTERNEREA PAM.VEGETAL PE TEREN CU PANTA
<20%,IN STRAT.UNIFORME CU GROSIMEA DE
10CM

014 TSH09A1	100 MP.	29.400
-------------	---------	--------

SEMANAREA GAZONULUI PE SUPRAFETE
ORIZONTALE SAU IN PANTA SUB 30% *

015 AUT1233	ORA	270.000
-------------	-----	---------

ORA PR.AUTOMACARA CU BRAT ZABRELE 4,5-5,
8 TF 2 SCHIMBURI

016 GA04B1	HM.	14.700
------------	-----	--------

ASIM- TEAVA DE OTEL IZOLATA CU
POLIETILENA EXTRUDATA IN 3 LAYERE (3MM)
CU GROSIME DE 8 MM, CU EXECUTIE
MECANIZATA A LANSARII DN 150 MM, TEREN
NORMAL

016 4587876	M	1474.410
-------------	---	----------

TEAVA DIN OTEL D 168.3X7.1 MM, L360N

017 GA08C1	M	50.000
------------	---	--------

asim -TUB DE PROTECTIE DIN TEAVA OTEL
323.9X10MM SR EN ISO 3183

017 3272021	M	43.000
-------------	---	--------

TEAVA OL SR EN ISO 3183 DN 323.9X8 MM

017 4582426	M	7.000
-------------	---	-------

TEAVA DE OL SR EN ISO 3183, DN 323.9X10
MM

=====

018	IZL06C1	MP.	57.650
-----	---------	-----	--------

IZOL.ANTICOR.EXEC.MAN.PE TRASEU TEVI
OTEL,CU PROT.EXT.BANDA PVC.IZOLATIE
FOARTE INTARITA

019	GD05C1	BUC.	75.000
-----	--------	------	--------

CURBA DE SUDARE MONTATA LA TEVI AVIND DN
= 6 TOLI

020	4521876	BUC.	75.000
-----	---------	------	--------

CURBA CMF DIN OL L360NE PSL2 SR EN 3183:
2020 IZOLATA CU IZOLATIE DE TIP INTARITA
CU PED 168.3X8 MM

021	IC52C1#	BUC.	283.000
-----	---------	------	---------

MANSON DE DILATARE PENTRU CONDUCTE DE
GAZE (DRESSER) CU DIAMTEURL DE 150 MM

021	4582591	BUC.	283.000
-----	---------	------	---------

MANSON TERMOCONTRACTIL TIP C50

022	M1L05D1	BUC.	283.000
-----	---------	------	---------

ASIM- CONTROLUL SUDURILOR

023	GC01E1	HM.	14.700
-----	--------	-----	--------

ASIM - PROBA DE PRESIUNE CONDUCTE

024	GC05E1	HM.	14.700
-----	--------	-----	--------

ASIM -PROBA DE REZIST. LA COND.CU DN=150

025	GB01E1%	BUC.	1.000
-----	---------	------	-------

ASIM- MONTARE PISTON CU PERII

025	4521877	BUC.	1.000
-----	---------	------	-------

PISTON CU PERII DN 150 MM

026	GC04H1	BUC.	15.000
-----	--------	------	--------

MONTAREA CONTROL SI DEMONT ECHIP LA
PROBA DE REZIST SI REGIM

=====

027	GD10A1%	BUC.	2.000
-----	---------	------	-------

LEGATURA CONDUCTEI NOI LA RETEAUA IN
FUNCTIUNE

028	TRA02A50	TONA	12.416
-----	----------	------	--------

TRANSPORTUL RUTIER AL MATERIALELOR,
SEMIFABRICATELOR CU AUTOCAMIONUL PE
DIST.= 50 KM.

029	GD08G1	BUC.	8.000
-----	--------	------	-------

CAPAC BOMBAT DIN TABLA DE OTEL SUDAT LA
TEVI

030	GA11A1%	BUC.	6.000
-----	---------	------	-------

ASIM- INSTALATIE DE AERISIRE CU SITA
DEWISS

031	IZL04A1	M	62.000
-----	---------	---	--------

ASIM -PROTEJ.CU INELE DISTANTIERS A
IZOLATIEI TEVII DE OTEL. CAPETE LA
SUBTRAVERSARI DE DRUM SI CF AVAND D DE
LA 200 PANA LA 400 MM (BUC)

031	4585877	BUC.	50.000
-----	---------	------	--------

INELE DISTANTIERS DN 200-400 MM

031	4528254	BUC.	12.000
-----	---------	------	--------

PRESETUPA METALICA PENTRU ETANSARE TEAVA
METALICA DN 150 MM MONTATA IN TUB
PROTECTOR DN 323.91X10 MM

032	RPIC02C#	M	42.000
-----	----------	---	--------

MONT TEVI APAR,NG,PT INSTAL,SUDAT,LA
LEGAT CORP SI APARAT INCALZ,PT CLAD LOC
SI SOC-CULT,D=1 1/2-2"

032	3312573	M	42.840
-----	---------	---	--------

TEAVA P235TR2 60.3X3.6

033	GD07B1%	BUC.	14.000
-----	---------	------	--------

RASUFLATOARE CU CAPAC MONTATA IN LUNGUL
CONDUCTELOR DN=2 1/2"-6" - MONTARE

034	GB09J1	BUC.	6.000
-----	--------	------	-------

ASIM- CAMIN MONITORIZARE SCURGERI-
MONTAJ

=====

034 4587528	BUC.	6.000
-------------	------	-------

CAMIN MONITORIZARE SCURGERI

035 DF18A1	BUC.	75.000
------------	------	--------

ASIM--PLANTARE STILPI PENTRU INDICATOARE
DE CIRCULATIE RUTIERA - BORNE SCHIMBARE
DIRECTIE

035 2806424	BUC.	75.000
-------------	------	--------

BORNA DE BETON SCHIMBARE DIRECTIE

036 ACD15D1	BUC.	1.000
-------------	------	-------

ASIM -CAMIN VANE CU ROBINET DE
SECTIONARE -MONTAJ

036 4528258	BUC.	1.000
-------------	------	-------

CAMIN DE VANE (DIM. 1.5X1.5X2M),
INCLUSIV ROBINET DE SECTIONARE DN 150 MM

037 ACD01J1	BUC.	1.000
-------------	------	-------

CAPAC SI RAMA STAS 2308-81 PENTRU CAMINE
CU PIESA SUPT CAROSABIL , DN 800 MM

038 YC01RON	LEI.	
-------------	------	--

ASIM-MASURI DE PUNERE IN SIGURANTA
CONDUCTA TRANSPORT TITEI - 1 BUC

039 \$22252	BUC.	1.000
-------------	------	-------

PROTECTIE CATODICA -U

- D E S C R I E R E :

>>> componenta 001

039 4152878	BUC.	15.000
-------------	------	--------

ANOZI DE SACRIFICU DIN ZINC

>>> componenta 002

039 4582500	BUC.	2.000
-------------	------	-------

IMBINARE MONOBLOC PN64 DN 150 MM

>>> componenta 003

039 4582501	BUC.	2.000
-------------	------	-------

MANSON TERMOCONTRACTIL PENTRU IMBINARI

=====
>>> componenta 004

039 4152879 BUC. 11.000
PRIZA DE POTENTIAL CU STEGULET YIP
"CONPET"

>>> componenta 005

039 7500270 M 140.000
CABLU DE ENERGIE CYY-F 1x6 mmp.

>>> componenta 006

039 4152880 M 200.000
CABLU CYY 1X25 MM

>>> componenta 007

039 4152881 BUC. 25.000
CONEXIUNE CABLU LA CONDUCTA

>>> componenta 008

039 4152882 M 2000.000
DCVG PENTRU IZOLATIE CONDUCTA

>>> componenta 009

039 NMB011749 ORA 135.000
PIF SISTEM PROTECTIE CATODICA

>>> componenta 010

039 4152883 BUC. 1.000
CUTIE CU REZISTOARE REGLABILE

040 TSC02C1 100 MC. 8.320
SAPATURA CU EXCAVAT.PE PNEURI 0,21-0,39
MC PAMINT UMIDIT.NATUR.DESC AUT.TER.CAT.
1

041 TSA02G1 M.C. 832.000
SAP.MAN.IN SPATII LIMIT.SUB 1M CU TALUZ
VERT.NESPR.IN PAM.COEZ.MIJ.SI F.COEZ.
ADINC.<1,5M T.F.TAR

042 RPGA32F# M 1360.000
ASIM-DEMONTAREA DIN PAMANT A TEVILOR DIN
OL PT. CONSTRUCTII AVAND DIAMETRUL DE:6
5/8"

=====

043	TRI1AA01C1	TONA	45.170
-----	------------	------	--------

INCARCAREA MATERIALELOR,GRUPA A-GRELE SI
MARUNTE,PRIN ARUNCARE RAMPA SAU TEREN-
AUTO CATEG.1

044	TSC26B1	100 MC.	1.000
-----	---------	---------	-------

DISLOC.PAM.DEPOZ.NECOMPAC.CU IMPING.LA
5M CU BULD.PE TRACT.DE 81-180CP.T.CAT.1
SAU 2

045	TSD01C1	M.C.	1996.800
-----	---------	------	----------

IMPRASTIEREA CU LOPATA A PAMINT.AFINAT,
STRAT UNIFORM 10-30CM.GROS CU SFARIM.
BULG.TEREN TARE

046	TSD04B1	M.C.	1664.000
-----	---------	------	----------

COMPACTAREA CU MAI.DE MINA A UMPLUT.
EXECUT.PE STRAT.CU UDAREA FIEC.STRAT DE
10CM GROS.T.COEZIV

047	AUT1233	ORA	280.000
-----	---------	-----	---------

ORA PR.AUTOMACARA CU BRAT ZABRELE 4,5-5,
8 TF 2 SCHIMBURI

048	TSE04B1	100 MP.	16.000
-----	---------	---------	--------

NIVELAREA SUPR.TEREN.SI PLATF.DE TERASM.
EXEC.CU BULDOZ.PE TRACT.81-180CP IN
TEREN CATEG.1 SI 2

049	TRA04A50	TONA	41.500
-----	----------	------	--------

ASIM-TRANSPORT RUTIER MATER.GRELE (
CONDUCTE NOI)

Cheltuieli directe din articole:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
Din care:					
Valoare aferenta utilaje termice			=		
Valoare aferenta utilaje electrice			=		

Detaliiere transporturi:
-Articole TRA

Alte cheltuieli directe:

-CONTRIBUTIE ASIGURATORIE PT.MUNCA

Total cheltuieli directe:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Cheltuieli indirecte:
Profit:

TOTAL GENERAL DEVIZ:
TVA

=====

TOTAL cu TVA

PROIECTANT

CONTRACTANT (OFERTANT)

DEVIZIER

SISTEM INFORMATIC PROIECTAT DE FIRMA I N F S E R V (Tel:2109807)

