

Formularul F3

Obiectivul: 0309 45330000 RETEA GAZE CONPET URLATI -
ORZOAIA
Obiectul: 0001 45330000 CONPET URLATI - ORZOAIA
Lista cu cantitatile de lucrari
Deviz oferta 309001 VARIANTA I

Categoria de lucrari: 0131

```
=====
= NR. SIMBOL ART.   CANTITATE      UM          PU MAT   VAL MAT   =
=   D E N U M I R E                                PU MAN   VAL MAN   =
=                                     A R T I C O L      PU UTI   VAL UTI   =
=                                     PU TRA   VAL TRA   =
= SPOR MAT MAN UTI      GR./UA    GR.TOT.          T O T A L   =
=====
001 TSH01A1          100 MP.        29.400
DEGAJAREA TERENULUI DE CORPURI STRAINE
```

002 TSA02G1 M.C. 453.480
SAP.MAN.IN SPATII LIMIT.SUB 1M CU TALUZ
VERT.NESPR.IN PAM.COEZ.MIJ.SI F.COEZ.
ADINC.<1,5M T.F.TAR

003 TSC02C1 100 MC. 10.580
SAPATURA CU EXCAVAT.PE PNEURI 0,21-0,39
MC PAMINT UMIDIT.NATUR.DESC AUT.TER.CAT.
1

004 TSC02C1 100 MC. 1.830
SAPATURA CU EXCAVAT.PE PNEURI 0,21-0,39
MC PAMINT UMIDIT.NATUR.DESC AUT.TER.CAT.
1- GROAPA DE POZITIE

005 GD11A1# M.C. 307.670
STRAT DE NISIP PENTRU PROTEJARE CONDUCTE
PE

006 TSD01C1 M.C. 1444.720
IMPRASTIEREA CU LOPATA A PAMINT.AFINAT,
STRAT UNIFORM 10-30CM.GROS CU SFARIM.
BULG.TEREN TARE

007 TSD04B1 M.C. 1203.930
COMPACTAREA CU MAI.DE MINA A UMPLUT.
EXECUT.PE STRAT.CU UDAREA FIEC.STRAT DE
10CM GROS.T.COEZIV

008 TRI1AA01C1 TONA 41.500
INCARCAREA MATERIALELOR,GRUPA A-GRELE SI
MARUNTE,PRIN ARUNCARE RAMPA SAU TEREN-
AUTO CATEG.1

009 TRA01A10P TONA 2695.250
TRANSPORTUL RUTIER AL PAMINTULUI SAU
MOLOZULUI CU AUTOBASCULANTA DIST.=10 KM

=====

010 GA09C1	M	7.000
------------	---	-------

ASIM- FORAJ ORIZONTAL DIRIJAT DN 400 MM

011 TSF01A1	MP.	378.240
-------------	-----	---------

SPRIJIN.DE MALURI CU DULAPI DE FAG ASEZ.
ORIZ.LAT.INTRE MAL.<1,5M,ADIN.0,0-2M,0,0
-0,2M INTRE DULA

012 MDTC4641100	BUC.	1.000
-----------------	------	-------

TRANSPORT UTILAJ 100KM-65123003-
AUTOMACARA 0,045-0,059MN,H.MAX.6,5M,DES.
MAX.5,5M,MOMENT MAX.15TF

013 TSH05A1	MP.	2940.000
-------------	-----	----------

ASTERNEREA PAM.VEGETAL PE TEREN CU PANTA
<20%,IN STRAT.UNIFORME CU GROSIMEA DE
10CM

014 TSH09A1	100 MP.	29.400
-------------	---------	--------

SEMANAREA GAZONULUI PE SUPRAFETE
ORIZONTALE SAU IN PANTA SUB 30% *

015 AUT1233	ORA	270.000
-------------	-----	---------

ORA PR.AUTOMACARA CU BRAT ZABRELE 4,5-5,
8 TF 2 SCHIMBURI

016 GA04B1	HM.	14.700
------------	-----	--------

ASIM- TEAVA DE OTEL IZOLATA CU
POLIETILENA EXTRUDATA IN 3 LAYERE (3MM)
CU GROSIME DE 8 MM, CU EXECUTIE
MECANIZATA A LANSARII DN 150 MM, TEREN
NORMAL

016 4587876	M	1474.410
-------------	---	----------

TEAVA DIN OTEL D 168.3X7.1 MM, L360N

017 GA08C1	M	50.000
------------	---	--------

asim -TUB DE PROTECTIE DIN TEAVA OTEL
323.9X10MM SR EN ISO 3183

017 3272021	M	43.000
-------------	---	--------

TEAVA OL SR EN ISO 3183 DN 323.9X8 MM

017 4582426	M	7.000
-------------	---	-------

TEAVA DE OL SR EN ISO 3183, DN 323.9X10
MM

=====

018	IZL06C1	MP.	57.650
-----	---------	-----	--------

ASIM-IZOL.ANTICOR.EXEC.MAN.PE TRASEU
TEVI OTEL,CU PROT.EXT.BANDA PE, INCL.
CURATARE

019	GD05C1	BUC.	75.000
-----	--------	------	--------

CURBA DE SUDARE MONTATA LA TEVI AVIND DN
= 6 TOLI

020	4521876	BUC.	75.000
-----	---------	------	--------

CURBA CMF DIN OL L360NE PSL2 SR EN 3183:
2020 IZOLATA CU IZOLATIE DE TIP INTARITA
CU PED 168.3X8 MM

021	IC52C1#	BUC.	283.000
-----	---------	------	---------

MANSON DE DILATARE PENTRU CONDUCTE DE
GAZE (DRESSER) CU DIAMTEURL DE 150 MM

021	4582591	BUC.	283.000
-----	---------	------	---------

MANSON TERMOCONTRACTIL TIP C50

022	M1L05D1	BUC.	283.000
-----	---------	------	---------

ASIM- CONTROLUL SUDURILOR

023	GC01E1	HM.	14.700
-----	--------	-----	--------

ASIM - PROBA DE PRESIUNE CONDUCTE

024	GC05E1	HM.	14.700
-----	--------	-----	--------

ASIM -PROBA DE REZIST. LA COND.CU DN=150

025	GB01E1%	BUC.	1.000
-----	---------	------	-------

ASIM- MONTARE PISTON CU PERII

025	4521877	BUC.	1.000
-----	---------	------	-------

PISTON CU PERII DN 150 MM

026	GC04H1	BUC.	15.000
-----	--------	------	--------

MONTAREA CONTROL SI DEMONT ECHIP LA
PROBA DE REZIST SI REGIM

=====

027	GD10A1%	BUC.	2.000
-----	---------	------	-------

LEGATURA CONDUCTEI NOI LA RETEAUA IN
FUNCTIUNE

028	TRA02A50	TONA	12.416
-----	----------	------	--------

TRANSPORTUL RUTIER AL MATERIALELOR,
SEMIFABRICATELOR CU AUTOCAMIONUL PE
DIST.= 50 KM.

029	GD08G1	BUC.	8.000
-----	--------	------	-------

CAPAC BOMBAT DIN TABLA DE OTEL SUDAT LA
TEVI

030	GA11A1%	BUC.	6.000
-----	---------	------	-------

ASIM- INSTALATIE DE AERISIRE CU SITA
DEWISS

031	IZL04A1	M	62.000
-----	---------	---	--------

ASIM -PROTEJ.CU INELE DISTANTIARE A
IZOLATIEI TEVII DE OTEL. CAPETE LA
SUBTRAVERSARI DE DRUM SI CF AVAND D DE
LA 200 PANA LA 400 MM (BUC)

031	4585877	BUC.	50.000
-----	---------	------	--------

INELE DISTANTIARE DN 200-400 MM

031	4528254	BUC.	12.000
-----	---------	------	--------

PRESETUPA METALICA PENTRU ETANSARE TEAVA
METALICA DN 150 MM MONTATA IN TUB
PROTECTOR DN 323.91X10 MM

032	RPIC02C#	M	42.000
-----	----------	---	--------

MONT TEVI APAR,NG,PT INSTAL,SUDAT,LA
LEGAT CORP SI APARAT INCALZ,PT CLAD LOC
SI SOC-CULT,D=1 1/2-2"

032	3312573	M	42.840
-----	---------	---	--------

TEAVA P235TR2 60.3X3.6

033	GD07B1%	BUC.	14.000
-----	---------	------	--------

RASUFLATOARE CU CAPAC MONTATA IN LUNGUL
CONDUCTELOR DN=2 1/2"-6" - MONTARE

034	GB09J1	BUC.	6.000
-----	--------	------	-------

ASIM- CAMIN MONITORIZARE SCURGERI-
MONTAJ

=====

034 4587528	BUC.	6.000
CAMIN MONITORIZARE SCURGERI		

035 DF18A1	BUC.	75.000
ASIM--PLANTARE STILPI PENTRU INDICATOARE DE CIRCULATIE RUTIERA - BORNE SCHIMBARE DIRECTIE		

035 2806424	BUC.	75.000
BORNA DE BETON SCHIMBARE DIRECTIE		

036 ACD15D1	BUC.	1.000
ASIM -CAMIN VANE CU ROBINET DE SECTIONARE -MONTAJ		

036 4528258	BUC.	1.000
CAMIN DE VANE (DIM. 1.5X1.5X2M), INCLUSIV ROBINET DE SECTIONARE DN 150 MM		

037 ACD01J1	BUC.	1.000
CAPAC SI RAMA STAS 2308-81 PENTRU CAMINE CU PIESA SUPT CAROSABIL , DN 800 MM		

038 DC04B1#	M	30.000
Taierea cu masina cu discuri diamantate a rosturilor de dilatatie si contractie in betonl de uzu		

039 DC04B1#	M	98.000
Taierea cu masina cu discuri diamantate a rosturilor de dilatatie si contractie in betonl de uzu		

040 DG06B1	M.C.	6.510
SPARG SI DESF BET CIM PE SUPRAF LIMIT PT POZARE CABL COND POD GURI, SCURG IN ALEI FUND DRUM		

041 TR11AA01A3	TONA	10.400
INCARCAREA MATERIALELOR, GRUPE A-GRELE SI MARUNTE, PRIN ARUNCARE RAMPA-VAGON CATEG. 3		

042 TRA01A20P	TONA	10.400
TRANSPORTUL RUTIER AL PAMINTULUI SAU MOLOZULUI CU AUTOBASCULANTA DIST.=20 KM		

=====

043	DA14A1	M.C.	6.510
FUNDATIE BETON CIMENT LA STRAZI ALEI SI			
PLATFORME CAROSABILE			

043	2100971	M.C.	6.562
BETON DE CIMENT B 300 STAS 3622			

044	TRA06A20	TONA	15.624
TRANSPORTUL RUTIER AL BETONULUI-			
MORTARULUI CU AUTOBETONIERA DE 5,5MC			
DIST. =20KM			

045	CB10A1	MP.	2.800
COFRAJE PT BET IN CUZINETI, FUND PAHAR SI			
DE UTILAJE, SIMPLE DIN PAN CU PLACAJ 8MM			
INCLUSIV SPIJI			

046	CC01C1	KG	334.000
MONTARE ARMATURI DIN OTEL BETON IN			
FUNDATII CONTI NUE, PLACI DE RADIERE, CU			
DIST DIN MASE PLASTICE			

046	6433560	KG	334.000
ARMATURI IN PREFABRICATE BETON OB37			
PESTE 10MM CALMAT BAREM			

047	CZ0301A1	KG	334.000
CONFECT.ARMAT.FASONARE BARE PT.FUNDATII			
IZOL.CONTINUI SI RADIERE IN ATEL.CENT.OB			
37 D=6-8MM			

048	TRA01A20	TONA	0.334
TRANSPORTUL RUTIER AL MATERIALELOR,			
SEMIFABRICATELOR CU AUTOBASCULANTA PE			
DIST.= 20 KM.			

049	DG05XC	MP.	10.500
DECAPARE ASFALT TURNAT PE FUNDATIE BETON			
COVOARE ASFALTICE LA RECE PINA LA 3CM			

050	TRI1AA01A3	TONA	0.504
INCARCAREA MATERIALELOR, GRUPA A-GRELE SI			
MARUNTE, PRIN ARUNCARE RAMPA-VAGON CATEG.			
3			

051	TRA01A20P	TONA	0.504
TRANSPORTUL RUTIER AL PAMINTULUI SAU			
MOLOZULUI CU AUTOBASCULANTA DIST.=20 KM			

=====

052	DA06A1	M.C.	2.620
STRAT AGREG NAT(BALAST)CILINDR CU FUNCT			
REZIST FILTRANT IZOL AERISIRE ANTCAPI CU			
ASTERNE MANUALE			

053	DA10A1	M.C.	2.620
STRAT RUTIER MATER GRAN STAB CU CIMENT			
SAU VAR SI ZGURA PRIN MET AMEST IN			
STATII FIXE AST MAN			

053	4358320	M.C.	2.628
Amestec pt. str.stabilizate exec.din			
nisip cu 3% var si 35% zgura granulata			

054	TRA01A20	TONA	8.925
TRANSPORTUL RUTIER AL MATERIALELOR,			
SEMIFABRICATELOR CU AUTOBASCULANTA PE			
DIST.= 20 KM.			

055	DB14D1#	MP.	1.580
Imbrac.de beton asfaltic cu agregat			
mare,exec.la cald,in gros.de 7cm cu			
asternere manuala			

055	3804003	TONA	0.261
Mixturi asfaltice ptr.str.baza exec.la			
cald cu bitum si agreg.concasate de 0-			
25mm in inst.TELTOMAT			

055	3803960	TONA	0.005
Nisip bituminat si dressing gras cu			
nisip 0-3mm si 4% bitum in inst.TELTOMAT			

056	DC07A1#	MP.	15.000
Amorsarea supraf.strat.de baza sau a			
imbrac.exist.in ved.aplic.unui strat de			
uzura din mixtura a			

057	DB20B1	MP.	15.000
ASFALT TURNAT PE PART CAROS GROS 4 CM			
ASTER MAN			

057	3256541	TONA	1.440
ASFALT TIP BADPS 31			

058	TRA06A20	TONA	1.701
TRANSPORTUL RUTIER AL BETONULUI-			
MORTARULUI CU AUTOBETONIERA DE 5,5MC			
DIST. =20KM			

=====

059 RPIF12B#	MP.	2.000
--------------	-----	-------

GRUNDUIT SI VOPSIT CU VOPSELE PE BAZA DE
ULEI, IN 2 STRATURI, CONDUCTE INSTAL, D EXT
> 60 MM

060 \$22252	BUC.	1.000
-------------	------	-------

PROTECTIE CATODICA -U

- D E S C R I E R E :

>>> componenta 001

060 4152878	BUC.	15.000
-------------	------	--------

ANOZI DE SACRIFICU DIN ZINC

>>> componenta 002

060 4582500	BUC.	2.000
-------------	------	-------

IMBINARE MONOBLOC PN64 DN 150 MM

>>> componenta 003

060 4582501	BUC.	2.000
-------------	------	-------

MANSON TERMOCONTRACTIL PENTRU IMBINARI

>>> componenta 004

060 4152879	BUC.	11.000
-------------	------	--------

PRIZA DE POTENTIAL CU STEGULET YIP
"CONPET"

>>> componenta 005

060 7500270	M	140.000
-------------	---	---------

CABLU DE ENERGIE CYY-F 1x6 mmp.

>>> componenta 006

060 4152880	M	200.000
-------------	---	---------

CABLU CYY 1X25 MM

>>> componenta 007

060 4152881	BUC.	25.000
-------------	------	--------

CONEXIUNE CABLU LA CONDUCTA

>>> componenta 008

060 4152882	M	2000.000
-------------	---	----------

DCVG PENTRU IZOLATIE CONDUCTA

=====
>>> componenta 009

060 NMB011749 ORA 135.000
PIF SISTEM PROTECTIE CATODICA

>>> componenta 010

060 4152883 BUC. 1.000
CUTIE CU REZISTOARE REGLABILE

061 TSC02C1 100 MC. 8.320
SAPATURA CU EXCAVAT.PE PNEURI 0,21-0,39
MC PAMINT UMIDIT.NATUR.DESC AUT.TER.CAT.
1

062 TSA02G1 M.C. 832.000
SAP.MAN.IN SPATII LIMIT.SUB 1M CU TALUZ
VERT.NESPR.IN PAM.COEZ.MIJ.SI F.COEZ.
ADINC.<1,5M T.F.TAR

063 RPGA32F# M 1360.000
ASIM-DEMONTAREA DIN PAMANT A TEVILOR DIN
OL PT. CONSTRUCTII AVAND DIAMETRUL DE:6
5/8"

064 TRI1AA01C1 TONA 45.170
INCARCAREA MATERIALELOR,GRUPA A-GRELE SI
MARUNTE,PRIN ARUNCARE RAMPA SAU TEREN-
AUTO CATEG.1

065 TSC26B1 100 MC. 1.000
DISLOC.PAM.DEPOZ.NECOMPAC.CU IMPING.LA
5M CU BULD.PE TRACT.DE 81-180CP.T.CAT.1
SAU 2

066 TSD01C1 M.C. 1996.800
IMPRASTIEREA CU LOPATA A PAMINT.AFINAT,
STRAT UNIFORM 10-30CM.GROS CU SFARIM.
BULG.TEREN TARE

067 TSD04B1 M.C. 1664.000
COMPACTAREA CU MAI.DE MINA A UMPLUT.
EXECUT.PE STRAT.CU UDAREA FIEC.STRAT DE
10CM GROS.T.COEZIV

068 AUT1233 ORA 280.000
ORA PR.AUTOMACARA CU BRAT ZABRELE 4,5-5,
8 TF 2 SCHIMBURI

069 TSE04B1 100 MP. 16.000
NIVELAREA SUPR.TEREN.SI PLATF.DE TERASM.
EXEC.CU BULDOZ.PE TRACT.81-180CP IN
TEREN CATEG.1 SI 2

=====

070 TRA04A50	TONA	41.500
--------------	------	--------

ASIM-TRANSPORT RUTIER MATER.GRELE (
CONDUCTE NOI)

Cheltuieli directe din articole:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Din care:
Valoare aferenta utilaje termice =
Valoare aferenta utilaje electrice =

Detaliiere transporturi:
-Articole TRA

Alte cheltuieli directe:

-CONTRIBUTIE ASIGURATORIE PT.MUNCA

Total cheltuieli directe:

GREUTATE	MATERIALE	MANOPERA	UTILAJ	TRANSPORT	TOTAL
----------	-----------	----------	--------	-----------	-------

Cheltuieli indirecte:
Profit:

TOTAL GENERAL DEVIZ:
TVA
TOTAL cu TVA

PROIECTANT CONTRACTANT (OFERTANT)

DEVIZIER

SISTEM INFORMATIC PROIECTAT DE FIRMA I N F S E R V (Tel:2109807)

