



- vopsea lavabila alb
- glet 2 straturi
- placare cu gips-carton 12,5 mm
- profile al. fixare gips-carton
- OSB
- folie bariera de vapori
- structura lemn
- vata minerala 15 cm
- placi tip "betopan"
- membrana anti-umiditate
- vata bazaltica 10 cm
- masa spaclu armata cu plasa
- finisaj exterior tabla prefaltuita pentru fatada prinsa cu bride si profile aluminiu



- vopsea lavabila alb
- glet 2 straturi
- placare cu gips-carton 12,5 mm
- profile al. fixare gips-carton
- structura lemn
- vata minerala 15 cm
- profile al. fixare gips-carton
- placare cu gips-carton 12,5 mm
- glet 2 straturi
- vopsea lavabila alb



- vopsea lavabila alb
- glet 2 straturi
- placare cu gips-carton 12,5 mm
- structura al.
- vata minerala 10 cm
- placare cu gips-carton 12,5 mm
- glet 2 straturi
- vopsea lavabila alb

02	23.11.2023	Beneficiar	Emis pentru executie
01	17.10.2023	Beneficiar	Emis pentru executie
00	13.09.2023	Beneficiar	Emis pentru comentarii
Nr. rev.	Data	Modificare solicitata de:	Denumirea modificarii

Verificator / Expert	Nume / Name	Semnatura / Signature	Cerinta / Requirement	Referat / Expertiza Nr. / Data / Reference / Expertise No. / Date
Proiectant general / General Designer	ROENGG CONSULTING SRL	ROENGG	TUV	Beneficiar / Client: CONPET S.A.
Proiectant de specialitate / Specialist Designer	S.C. INRO CONSTRUCT S.R.L.			Titlul proiectului / Project Title: REABILITARE, EXTINDERE SI ETAJARE CLADIRE SEDIU ADMINISTRATIV STATIE POMPAE URLATI
Proiectat / Designed	L. E.	Semnatura / Signature	Scara / Scale: 1:50	Titlul plansei / Drawing Title: PLAN ETAJ
Verificat / Checked	L. E.		Data / Date: 23.11.2023	Nr. Desen / Drawing No.: 10212022-RNG-DTDS-ARH-PLN-001
Aprobat / Approved	S. D.			Faza / Project Phase: DDE Nr. pag. / Page No.: 1/1