



EXTRAS DE LAMINATE - RIGLESI DETALII DE MONTAJ PERGOLE							
POZ	DENUMIRE	STAS	Buc.	MATERIAL	DIMENSIUNI	MASA / BUC.	/TOTAL
P1	PROFIL	EN 10219-2	10	S235JR	TV:150X150X5-5050	112.62	1126.15
P2	CAPAC	SREN 10029:2011	20	S235JR	6x150-150	1.06	21.20
P3	PROFIL	EN 10219-2	2	S235JR	TV:150X150X5-11000	245.30	490.60
P4	ANCORA CHIMICA M24+A24	SREN 15048-1:2007	80	gr. 8.8	2M24+A24	0.50	40.00
Total KG -							1677.95
ELECTROZI 2.5 %							41.95
TOTAL KG							1719.89



NOTA: Debitarea pieselor se va face numai dupa verificarea dimensiunilor in teren.

02	23.11.2023	Beneficiar	Emis pentru executie	
01	17.10.2023	Beneficiar	Emis pentru executie	
00	13.09.2023	Beneficiar	Emis pentru comentarii	
Nr. rev.	Data	Modificare solicitata de:	Denumirea modificarii	
-	-	-	-	-
Verificator / Expert	Nume / Name	Semnatura / Signature	Cerinta / Requirement	Referat / Expertiza Nr. / Data / Reference / Expertise No. / Date
Proiectant general /General Designer ROENGG CONSULTING SRL RO 24611389 / 0344 806 979 / contact@roengg.com				Beneficiar / Client: CONPET S.A.
Proiectant de specialitate / Specialist Designer S.C. INRO CONSTRUCT S.R.L.				Titlul proiectului / Project Title: REABILITARE, EXTINDERE SI ETAJARE CLADIRE SEDIU ADMINISTRATIV STATIE POMPAE URLATI
	Nume / Name	Semnatura / Signature	Scara / Scale:	Titlul plansei / Drawing Title:
Proiectat / Designed	F. R.		1:10; 1:20; 1:50	CADRU METALIC PERGOLA SI DETALII
Verificat / Checked	F. R.		Data / Date:	Nr. Desen / Drawing No.:
Aprobat / Approved	S. D.		23.11.2023	10212022-RNG-DTDS-CIV-DTD-013
				Faza / Project Phase:
				DDE
				Nr. pag. / Page No:
				1/1