



EXTRAS DE LAMINATE - Stalp S1- PERGOLE							
POZ	DENUMIRE	STAS	Buc.	MATERIAL	DIMENSIUNI	MASA / BUC.	/TOTAL
P1	PROFIL	EN 10219-2	1	S235JR	TV:150X150X5-3825	85.30	85.30
P2	PLACA	SREN 10029:2011	1	S235JR	15x350-350	14.42	14.42
P3	RIGIDIZARE	SREN 10029:2011	4	S235JR	8x100-135	0.85	3.39
P4	PLACA	SREN 10029:2011	1	S235JR	15x200-200	4.71	4.71
Total KG -							107.82
ELECTROZI 2.5 %							2.70
TOTAL KG/buc			1				110.52
TOTAL KG /20 buc			20				2210.37

NOTA: Debitarea pieselor se va face numai dupa verificarea dimensiunilor in teren.

02	23.11.2023	Beneficiar	Emis pentru executie	
01	17.10.2023	Beneficiar	Emis pentru executie	
00	13.09.2023	Beneficiar	Emis pentru comentarii	
Nr. rev.	Data	Modificare solicitata de:	Denumirea modificarii	
-	-	-	-	
Verificator / Expert	Nume / Name	Semnatura / Signature	Cerinta / Requirement	Referat / Expertiza Nr. / Data / Reference / Expertise No. / Date
Proiectant general / General Designer			Beneficiar / Client:	
ROENGG CONSULTING SRL			CONPET S.A.	
RO 24611389 / 0344 806 979 / contact@roengg.com				
Proiectant de specialitate / Specialist Designer			Titlul proiectului / Project Title:	
S.C. INRO CONSTRUCT S.R.L.			REABILITARE, EXTINDERE SI ETAJARE CLADIRE SEDIU ADMINISTRATIV STATIE POMPA URLATI	
		Semnatura / Signature	Scara / Scale:	Titlul plansei / Drawing Title:
Proiectat / Designed	F. R.		1:10; 1:20	STALP METALIC PERGOLA
Verificat / Checked	F. R.		Data / Date:	Nr. Desen / Drawing No.:
Aprobat / Approved	S. D.		23.11.2023	10212022-RNG-DTDS-CIV-DTD-014
				Faza / Project Phase:
				DDE
				Nr. pag. / Page No:
				1/1